HAGEN FARM SITE, WI GROUNDWATER CONTROL OPERABLE UNIT

92103

DECLARATION FOR THE RECORD OF DECISION

Site Name and Location

Hagen Farm Site, Groundwater Control Operable Unit Dane County, Wisconsin

Statement of Basis and Purpose

This decision document represents the selected remedial action for the Hagen Farm Site (the "Site"), in Dane County, Wisconsin, Groundwater Control Operable Unit, which was chosen in accordance with the Comprehensive Environmental Response Compensation, and Liability Act of 1980 (CERCLA), as amended by the Superfund Amendments and Reauthorization Act of 1986 (SARA) and, to the extent practicable, the National Oil and Hazardous Substances Pollution Contingency Plan (NCP).

This decision is based on the Administrative Record for the Hagen Farm site.

The State of Wisconsin concurs with the selected remedy on the condition that, at the time that the proposed treatment design is finalized, the State determines that the proposed effluent discharge limits and discharge location are acceptable to the State.

Assessment of the Site

Actual or threatened releases of hazardous substances from this Site, if not addressed by implementing the response action selected in this Record of Decision (ROD), may present an imminent and substantial endangerment to public health, welfare, or the environment.

Description of Remedy

This Groundwater Control Operable Unit is the second of two operable units for the Site. For purposes of this ROD, the "Site" is defined as the area within the Hagen Farm property boundary and the contaminant plume. The selected remedial action for this operable unit addresses the groundwater contamination by remediation of contaminated groundwater. For purposes of this ROD, "on-property groundwater" is defined as contaminated groundwater on and in the immediate vicinity of the main waste disposal area and "off-property groundwater" is defined as contaminated groundwater

at any location within the plume other than in the area defined as on-property groundwater.

The major components of the selected remedy include:

- * Monitoring of all private wells located around the Site;
- * Pre-treatment of extracted on- and off-property groundwater;
- * Extraction and treatment of groundwater;
- * Treatment of on-property groundwater using Activated Sludge Biological Treatment;
- * Treatment of off-property groundwater using a treatment technology to be determined during the design phase;
- * Discharge of treated groundwater to wetlands or the Yahara River;
- * Treatment and disposal of sludges generated from the groundwater treatment and treatment of off-gas emitted from the treatment process;
- * Deed and access restrictions to prevent installation of drinking water wells within the vicinity of the disposal areas and off-property; and
- * Implementation of a bench scale study to determine the effect of nutrients and/or oxygen on contaminated groundwater. If the bench scale study shows positive results, a pilot study would be conducted, with the ultimate goal of enhancing the selected remedy with an insitu groundwater bioremediation system.

STATUTORY DETERMINATIONS

The selected remedy is protective of human health and the environment, complies with Federal and State environmental requirements that are legally applicable or relevant and appropriate to the remedial action, and is cost effective. This remedy utilizes permanent solutions and alternative treatment technologies to the maximum extent practicable and satisfies the statutory preference for remedies that employ treatment that reduces toxicity, mobility, or volume as a principal element.

Because this remedy will result in hazardous substances remaining on-site, a review will be conducted within five years after commencement of the remedial action to ensure that the remedy continues to provide adequate protection of human health and the environment.

Valdas V. Adamkus Regional Administrator

RECORD OF DECISION DECISION SUMMARY HAGEN FARM SITE GROUNDWATER CONTROL OPERABLE UNIT DANE COUNTY, WISCONSIN

Prepared By:

U.S. Environmental Protection Agency

Region V

Chicago, Illinois

September, 1992

ROD SUMMARY HAGEN FARM SUPERFUND SITE GROUNDWATER CONTROL OPERABLE UNIT DANE COUNTY, WISCONSIN

TABLE OF CONTENTS

I.	SITE NAME, LOCATION, AND DESCRIPTION	3
II.	SITE HISTORY AND ENFORCEMENT ACTIVITIES	5
III.	COMMUNITY RELATIONS ACTIVITIES	9
VI	SCOPE AND ROLE OF RESPONSE ACTION	10
v.	SUMMARY OF SITE CHARACTERISTICS	11
VI.	SUMMARY OF SITE RISKS	12
VII.	DOCUMENTATION OF SIGNIFICANT CHANGES	20
VIII.	DESCRIPTION OF REMEDIAL ALTERNATIVES	20
IX.	SUMMARY OF THE COMPARATIVE ANALYSIS OF ALTERNATIVES	26
х.	THE SELECTED REMEDY	33
XI.	STATUTORY DETERMINATIONS SUMMARY	35

ROD SUMMARY HAGEN FARM SUPERFUND SITE GROUNDWATER CONTROL OPERABLE UNIT DANE COUNTY, WISCONSIN


I. SITE LOCATION AND DESCRIPTION

The Hagen Farm Site (the Site) is located at 2318 County Highway A, approximately one mile east of the City of Stoughton, Dane County, Wisconsin. The Site is defined as the area within the Hagen Farm property boundary and the contaminant plume. The property is approximately 28 acres in size and is located in the northeast quarter of the southeast quarter of Section 10, Township 5 North, Range 11 East. Within the property boundary is approximately 10 acres of disposal area. The Site, as a whole, is situated in a rural surrounding that is dominated largely by sand and gravel mining and agriculture. Sand and gravel mining operations are located northwest, northeast, and south of the Site. The Stoughton Airfield is located adjacent to the northwest corner of the Site. County Highway "A" passes just south of the property boundary (See Figure 1).

The City of Stoughton's municipal wells are located approximately two miles to the west. Three private wells are located approximately 1000 feet west of the Site, and eight private wells are located within 4,000 feet downgradient from the Site based on hydrogeology information obtained during investigation at the Site (See Section V below). The private wells located at the Site were abandoned in accordance with NR 112 and are no longer in use. Approximately 350 people reside within one mile of the Site.

The Site is located in the Yahara River watershed, in an area of flat to gently rolling topography. The Yahara River is located approximately 1.3 miles to the west and flows in a southerly direction. The Site does not lie within the 100-year flood plain. The land surface generally slopes toward the Yahara River from topographically high areas located to the northeast and east. Surface-water drainage in the area is generally poorly developed, apparently due to permeable surface soils. The only substantial surface water bodies in the area are Sundby's pond located approximately 1/2 mile south of the Site and the Yahara River. An on-Site ditch is located at the southeast corner of the property which flows to a wetland. This wetland is located directly south of the Site. There is no designated Wisconsin State significant habitat, or historic landmark site directly or potentially affected. No endangered species are known to inhabit the Site.

The Site is located in an area dominated by glacial outwash deposits, which extend approximately one-half mile to the northeast. These deposits are dominated by sand and gravel. Beyond this, ground moraine and occasional drumlins are encountered. Lacustrine deposits associated with Glacial Lake



Yahara are located approximately one-eighth of a mile south. Bedrock, primarily sandstone and dolomite, underlie the glacial deposits in this area. Bedrock generally slopes from the west to southwest, toward a preglacial valley associated with the Yahara River. The depth to bedrock ranges from 50 to 80 feet near the Site. Groundwater is present approximately 10 to 40 feet below ground surface near the Site. Groundwater flow is predominantly to the south-southwest, toward the Yahara River, a regional groundwater discharge zone. Estimated groundwater velocities ranged from 1.2 ft/yr to 145 ft/yr.

The current Site topography is the result of sand and gravel mining and waste disposal activities. Prior to these activities, the ground surface probably sloped from the existing topographically high area located west and northwest toward the southeast and east. The excavated area in the northwest corner of the property is flat. This flat area is separated by a ridge from the water-filled depression located to the northeast.

Within the Site's "area of contamination" (AOC), waste disposal took place within three subareas. These subareas are A (6 acres, located in the southern portion of the property), B and C (1.5 acres each, located in the northeastern portion) (See Figure 2). All three subareas reside within the Site's formally defined AOC. Subareas B and C have been consolidated into the disposal area A. Disposal area A has been capped and vegetated. These consolidation and capping activities were conducted as part of the Source Control Operable Unit (see ROD in this matter dated September 17, 1990).


II. SITE HISTORY AND ENFORCEMENT ACTIVITIES

The Site was operated as a sand and gravel pit prior to the late 1950s. Observations suggest gravel operations encompassed an area bounded by the current access road to the east, the former Schroeter property boundary to the west, and the current property boundary to the north (See Figure 2). Mining operations reportedly terminated approximately 14 to 18 feet below ground surface. Excavation may have ceased at this depth due to the presence of groundwater, more fine grained materials, or a change in sand and gravel quality.

The gravel pit was then used for disposal of waste materials from the late 1950s to the mid-1960s. During the period that the Site was operated as a disposal facility, the property was owned by Nora Sundby, since deceased. The property was then purchased from Nora Sundby by Orrin Hagen in November 1977. The Site is currently owned by Waste Management of Wisconsin, Incorporated (WMWI). The Site was operated by City Disposal Corporation. City Disposal Corporation was subsequently purchased by WMWI. City Disposal was also the transporter of much of the waste that was deposited at the Site. It is known

Figure 2 Site Diagram Hagen Farm Site Dunkirk Township, Wisconsin

(Not To Scale)



JE

Prepared by Jacobs Engineering Group Inc. Chicago for the U.S. Environmental Protection Agency, 7/22/90

Drawn AH Checked DS

that Uniroyal, Incorporated (Uniroyal) generated industrial waste, some of which was deposited at the Site beginning sometime in 1962 and continuing through August 1966.

Waste solvents and other various organic materials, in addition to the municipal wastes, were disposed of at the Site, including acetone, butyl acetate, 1-2-dichloroethylene, tetrahydrofuran, solid vinyl, sludge material containing methyl ethyl ketone and xylenes, and toluene. In a 103(c) Notification submitted to the United States Environmental Protection Agency (U.S. EPA) by Uniroyal, in June 1981, Uniroyal indicated that F003 and F005 wastes (spent non-halogenated solvents), which are hazardous wastes within the meaning of the Resource Conservation and Recovery Act (RCRA), 42 U.S.C. 6901, also were disposed of at the Site. This site stopped accepting waste in 1966, prior to regulation of hazardous waste disposal by RCRA Subtitle C.

Beginning in November 1980, in response to complaints received from local residents, the Wisconsin Department of Natural Resources (WDNR) began conducting groundwater sampling at nearby private water supply wells. Sampling of the on-Site monitoring wells during the period 1980-1986 indicated certain organic compounds were present in the groundwater, including benzene, ethylbenzene, tetrahydrofuran (THF), xylenes, and toluene.

In addition, nearby private water supplies on adjacent properties also contained detectable levels of volatile organic compounds (VOCs). The private wells located on adjacent properties had been impacted by acetone, THF, vinyl chloride, xylene, trans-1,2-dichlorethene, and trichloroethylene.

In 1983, the State of Wisconsin brought an enforcement action for abatement of a public nuisance against WMWI and Uniroyal. At the same time, nearby residents to the Site brought a civil action against WMWI and Uniroyal, seeking civil damages for reduced property values and potential health hazards resulting from groundwater and well contamination. The State of Wisconsin obtained a dismissal of its 1983 enforcement action against WMWI and Uniroyal after the Site was listed on the National Priorities List (NPL). In 1986, the parties to civil litigation brought by the nearby residents to the Site against WMWI and Uniroyal reached a settlement. The exact terms of the settlement are confidential. It is known, however, that one of the terms of the settlement required WMWI to purchase the Site property from Orrin Hagen, as well as other property located adjacent to the Site. Upon acquiring these properties, WMWI razed the structures constructed thereon.

The Site was proposed for inclusion on the NPL on September 18, 1985. The Site was placed on the NPL in July 1987. Subsequently, WMWI and Uniroyal, the two potentially responsible parties (PRPs) named by U.S. EPA in connection with the Site to

date, entered into an Administrative Order by Consent (U.S. EPA Docket No. VW 87-C-016, dated September 14, 1987) (the Consent Order) with U.S. EPA and WDNR. In the Consent Order, WMWI and Uniroyal agreed to conduct a Remedial Investigation and Feasibility Study (RI/FS) at the Site. Accordingly, in July 1988, upon U.S. EPA approval, in consultation with the WDNR, of the required Work Plans, fieldwork at the Site commenced.

Two operable units (OUs) have been defined for the Site. OU I, which is the Source Control Operable Unit (SCOU), is intended to address waste refuse and sub-surface soils (Waste/sub-Soils) at disposal area A and the two smaller disposal areas B and C. OU II, which is the Groundwater Control Operable Unit (GCOU), is intended to address the contaminated on- and off-property groundwater at the Site. For purposes of this ROD, "on-property groundwater" is defined as contaminated groundwater on and in the immediate vicinity of the main waste disposal area and "off-property groundwater" is defined as contaminated groundwater at any location within the plume other than in the area defined as on-property groundwater. The OU approach was agreed upon after discussions among U.S. EPA, WDNR, and the PRPs during the early phase of the implementation of the Work Plan for the RI. This ROD is developed for the GCOU, which is OU II.

The RI for the SCOU was completed in early 1989, and the ROD was signed on September 17, 1990. An Explanation of Significant Differences was issued in April of 1991. Subareas B and C were consolidated into the disposal area A and the construction of the Landfill Cover over the main disposal area A, which is one of the components of the selected remedy for the SCOU, was completed in May 1992. Prior to the implementation of the Landfill Cover, wastes from areas B and C were consolidated into the main disposal area A. The implementation of In-Situ Vapor Extraction, which is also part of the selected remedy for the SCOU, was initiated in May 1992. The RI for the GCOU was initiated in July 1989 and the final RI report was submitted in November 1991. An Alternative Array was prepared in July 1991, which provided a preliminary description of the technical methods under consideration for cleaning up the groundwater. Based on the evaluation and screening of technical methods available for addressing the groundwater contamination in the Alternative Array, a draft Feasibility Study (FS) report was submitted in October 1991. The draft FS was revised in order to include off-property contaminated groundwater in January 1992, and finalized in April 1992. The FS Report for the GCOU final alternatives under consideration the outlines correcting contamination problems found in the groundwater, and provides a thorough evaluation of each alternative.

III. COMMUNITY RELATIONS ACTIVITIES

Upon the signing of the Consent Order in July 1987, U.S. EPA held a 30-day public comment period. A press release was sent to all local media and advertisements were placed.

A Community Relations Plan for the Site was finalized in July 1988. This document lists contacts in the government and interested parties throughout the local communities. It also establishes communication pathways to ensure timely dissemination of pertinent information.

An RI "Kickoff" meeting was held on July 14, 1988 to explain the RI process. A fact sheet was developed in conjunction with this meeting. Advertisements were placed in the Madison Capital Times and Stoughton Courier-Hub and a press release was sent to all local media.

A press release was sent to local media on March 27, 1989 to update the community on the progress of Dane County, Wisconsin Superfund sites, including Hagen Farm.

A public meeting was held on July 27, 1989 to explain the findings of the RI and the operable unit approach. A fact sheet was developed in conjunction with this meeting. Advertisements were placed to announce the meeting and a press release was sent to all local media. Prior to the public meeting, U.S. EPA representatives held a separate briefing for Town officials.

A public meeting was held on August 2, 1990, to present the recommended remedy for the SCOU. Advertisements were placed to announce the meeting and a press release was sent to all local media. A public comment period was held from July 11, 1990, to August 10, 1990. All comments received by U.S. EPA during the public comment period and at the public meeting were addressed in the Responsiveness Summary of the SCOU ROD.

A public meeting was held on August 29, 1991, to provide the public with an update on the progress for the SCOU and the GCOU at the Site. A fact sheet was developed in conjunction with this meeting. Advertisements were placed to announce the meeting and a press release was sent to all local media.

The RI/FS and the Proposed Plan for the GCOU were released to the public in May 1992. All of these documents were made available in the information repositories maintained at the Stoughton Public Library and Klongland Realty. An administrative record file containing these documents and other site-related documents was placed at the Stoughton Public Library. The notice of availability of these documents was published in the Stoughton Courier-Hub, Wisconsin State Journal, and Madison Capital Times on May 27, 1992. Press releases were

also sent to all local media. A public comment period was held from June 1, 1992 to July 1, 1992. The request for an extension of the comment period was made and the public comment period was extended until July 31, 1992. In addition, a public meeting was held on June 11, 1992 to present the results of the RI/FS and the preferred alternative as presented in the Proposed Plan for the Site. All comments received by U.S. EPA during the public comment period are addressed in the Responsiveness Summary which is the third section of this ROD.

As sampling results from private wells became available, U.S. EPA wrote letters to the property owners to inform them of these results. These letters were mailed in September 1989 and December 1990.

IV. SCOPE AND ROLE OF RESPONSE ACTION

As discussed in Section II above, U.S. EPA has divided the Site into two operable units. The SCOU addresses waste refuse and sub-surface soils at disposal area A and the two smaller disposal areas B and C. The GCOU, which is the subject of this ROD, is intended to address the contaminated on-and off-property groundwater at the Site.

- U.S. EPA identified contaminated on- and off-property groundwater as posing potential risks to human health and the environment. To address these risks, U.S. EPA developed the following remedial objectives for the GCOU based on the data obtained during the RI:
 - 1) Restore groundwater so that contamination levels meet appropriate Federal and State groundwater quality standards;
 - 2) Stop the flow of contaminated groundwater downgradient of the Site and to the Yahara River; and
 - 3) Prevent the flow of contaminated groundwater to residential wells.

This ROD was developed to meet these objectives and it addresses the contamination problems identified in the GCOU, namely the on- and off-property groundwater contamination at the Site. This response action is being implemented to protect human health and the environment from risks posed by the contamination problems.

This present response action, by addressing contaminated on- and off-property groundwater, is fully consistent with all future site work, including the on-going Remedial Design and Remedial Action (RD/RA) for the SCOU at the Site.

V. SUMMARY OF SITE CHARACTERISTICS

In November 1991, an RI Report for the GCOU was completed under the guidance and oversight of U.S. EPA and WDNR. The RI for the GCOU was to determine the nature and extent of contamination in the groundwater, and evaluate possible exposure pathways. The report summarized all soil-boring, surface water, on- and off-property groundwater, private well, pump test, and treatability study analytical data that had been collected. The RI report should be consulted for a more thorough description of the Site characteristics.


The following are the results of the RI at the Site:

- The uppermost aquifer at the Site is the glacial sand and gravel aquifer. This aquifer is unconfined with groundwater present approximately 10 to 40 feet below ground surface near the Site. The sandstone bedrock aquifer is located below the glacial sand and gravel aquifer. The saturated thickness of the unconsolidated sand and gravel aquifer generally ranges from 30 to 40 feet on site and 50 to 100 feet off site. The thickness of the bedrock aquifer is unknown. Based on the contact of the sand and gravel aquifer with the bedrock aquifer and the insignificant difference between water levels in the sand and gravel and bedrock wells, it appears that the two aquifers are hydraulically connected.
- Groundwater flow immediately beneath the main disposal area (Area A) is predominantly toward the southeast, but then rotates to a southerly and southwesterly direction immediately downgradient of disposal area A. Groundwater flow south of County Highway A appears to be generally southerly to southwesterly, with fairly uniform horizontal gradients. Groundwater velocities ranged from 1.2 to 145 feet per year.
- It does not appear that Sundby's pond functions as a local groundwater discharge area; groundwater flow appears to be horizontal or slightly downward beneath the pond. Data also indicate that the nearby drainage ditch is probably not a potential groundwater discharge point.
- The constant rate pumping test was run for 33 hours. During this test, 119,000 gallons were pumped from the aquifer resulting in a cone of depression extending out approximately 400 feet. This test indicates that the aquifer behaves as an unconfined aquifer with some degree of connection to the sandstone bedrock. Results showed an average transmissivity of 24,000 gallons per day per foot.

- The contaminants causing the most concern are VOCs. The elevated levels of VOCs detected in groundwater were THF (630,000 parts per billion (ppb)), ethylbenzene (4,400 ppb), toluene (2,700 ppb), and xylenes (37,000 ppb). Benzene (8 ppb), 1,1-dichloroethene (1 ppb), and vinyl chloride (77 ppb) were also detected in the groundwater. Inorganic compounds such as arsenic (25.2 ppb), barium (1,570 ppb), iron (17,000 ppb), lead (6 ppb), manganese (3,300 ppb), and mercury (6.5 ppb) were also found in the groundwater. Aroclor-1242 (0.25 ppb), arsenic (31.9 ppb), lead (997 ppb), cadmium (35.6 ppb), chromium (109 ppb), and mercury (1.0 ppb) were detected in the leachate from the landfill.
- The occurrence, concentration, and distribution of THF suggest there is a THF plume originating in the south-central section of disposal area A which extends downgradient (south) approximately 3,600 feet to between test boring #1 and well nest #34 (See figure 3).
- Private wells determined to be potential receptors were sampled in September 1989, August 1990 and September 1991.
 VOCs were not detected in private well samples collected during this investigation.
- A treatability study was conducted during the on-property pump test. The results of the treatability study indicate that air stripping can attain removal levels as high as 40 percent of the THF concentration in the sample tested. It is estimated that a cascade aeration system will remove up to 30 percent of the THF, with higher removal efficiencies for other VOC contaminants. Granular activated carbon (GAC) is an effective technology to remove VOCs by itself and also in combination with biological treatment. However, two of the contaminants, THF and 2-butanone, are not readily adsorbable. An activated sludge system can remove up to 99 percent of the THF and other organic compounds in the groundwater. UV-chemical oxidation should remove up to 99 percent of the contaminants.

VI. SUMMARY OF SITE RISKS

The baseline risk assessment was conducted to characterize the current and potential future threat to public health and the environment posed by chemicals in the groundwater originating at, or migrating from the Site. Both current and potential future-use conditions were examined in the baseline risk assessment. Under current conditions, the Site was assessed in the absence of remedial action for groundwater.



A risk assessment consists of four primary parts: identifying chemicals and other contaminants of concern; assessing pathways through which humans, plants, and animals could be exposed to contamination; assessing the toxicity of the contaminants; and characterizing cancerous and non-cancerous health effects on humans.

a. Human Health Risks

1. Contaminant Identification

The first step of the risk assessment was to select chemicals and other contaminants of potential concern for detailed evaluation. This was conducted by summarizing and evaluating RI data, including a consideration of naturally occurring background levels and the presence of chemicals in blank samples. Based on this evaluation, 56 chemicals of potential concern were selected for detailed assessment. These chemicals were considered most likely to be of concern to human health and the environment. The following compounds were selected as the chemicals and other contaminants of potential concern:

Organic Compounds

Metals

Acetone Benzoic acid 2-Butanone Chloromethane 1,4-Dichlorobenzene 4,4'-DDE Diethylphthlalate Ethylbenzene Naphthlalene Phenol Toluene Vinyl chloride	Benzene Benzyl alcohol Chlorobenzene 1,1-Dichloroethene 1,2-Dichloroethene Dieldrin 2,4-Dimethylphenol 4-Methylphenol Di-n-octylphthalate Tetrahydrofuran Vinyl acetate Xylenes (total)	Arsenic Barium Copper Manganese Mercury Nickel Vanadium Zinc
--	---	---

These contaminants were detected in both on- and off-property groundwater. Table 1 identifies the maximum concentration of contaminants in groundwater.

2. Exposure Assessment

An exposure assessment was conducted to identify potential pathways of exposure under current and future Site and surrounding land-use conditions. The following pathways were selected for detailed evaluation under current use conditions (Although no current private wells located around and downgradient of the Site are impacted by the contaminated groundwater, the assumptions were made that the private wells located in the near and far downgradient of the Site might be impacted due to the potential for groundwater flow changes.):

TABLE 1 Hagen Farm Site Groundwater Contamination Maximum Levels Detected/Groundwater Cleanup Standards

Compounds	Maximum Concentration (ug/l)		Standards (ug/L)			BD
	On-Property	Off-Property	ES	PAL	MCL	
<u>Organic</u>						
Benzene	8	ND	5	0.067	5	ND
1,1-Dichloroethene	1	ND	7	0.024	7	ND
Ethylbenzene	4,400	NĎ	1,360	272	700	ND
Tetrahydrofuran	630,000	1,200	50	10	NA	ND
Toluene	2,700	ND	343	68.6	1,000	ND
Xylenes	37,000	ND	620	124	10,000	ND
Vinyl Chloride	77	5	0.2	0.0015	2	ND
Inorganic						
Arsenic	25.2	ND	50	5	50	ND
Barium	1,570	ND	1,000	200	2,000	37
Iron	17,000	ND	300	150	300¹	ND
Lead	6.	5.6	50	5	15²	ND
Manganese	3,330	ND	50	25	NA	ND
Mercury	6.5	ND	2	0.2	2	ND

ES: Enforcement Standard, NR 140, WAC PAL: Preventive Action Limit, NR 140, WAC

MCL: Maximum Contaminant Level, Safe Drinking Water Act

BD: Background Level ND: Not-Detected

NA: Not Available

¹ Secondary MCL

² Action Level value

- Ingestion of groundwater; and
- Inhalation of VOCs by residents located near and far downgrdient of the Site while showering.

Under future-use conditions, the following pathways were selected for evaluation:

- Ingestion of groundwater by a future resident on the Site; and
- Inhalation of VOCs while showering by a future residents on the Site.

For the ingestion of groundwater by current and future residents, adult residents were assumed to weigh 70 kg and ingest two liters of water per day, 350 days per year and to live in the same location for 30 years of their 70-year expected lifetime. For the inhalation of VOCs while showering, an exposure time of 17 minutes, a frequency of exposure of 350 days per year, and a duration of exposure of 30 years were assumed.

The maximum concentration of contaminants of concern was used for groundwater to calculate the risk. For the inhalation exposures while showering, the exposure point concentrations were calculated using a shower model.

Toxicity Assessment

The harmful effects, or toxicity, of a chemical in terms of its potential cancerous and non-cancerous health effects were evaluated. Research was conducted to determine the toxicity of chemicals, and the results and conclusions of this research were used in the evaluation of the toxicity of Site-related contamination. In the research of a chemical's toxicity, the effects of low levels of chemical exposure on people in the workplace are studied over long periods of time, and test animals are studied in laboratories, where animals are exposed to varying levels of chemicals over different lengths of time.

Cancer slope factors have been developed by U.S. EPA's Carcinogen Assessment Group for estimating excess lifetime cancer risks associated with exposure to potentially carcinogenic chemicals. Slope factors, which are expressed in units of (mg/kg-day)⁻¹, are multiplied by the estimated intake of a potential carcinogen, in mg/kg-day, to provide an upper-bound estimate of the excess lifetime cancer risk associated with exposure at that intake level. The term "upper bound" reflects the conservative estimate of the risks calculated from the cancer slope factor. Use of this approach makes underestimation of the actual cancer risk highly unlikely. Cancer slope factors

are derived from the results of human epidemiological studies or chronic animal bioassays to which animal-to-human extrapolation and uncertainty factors have been applied. Table 2 contains the cancer slope factors for carcinogenic contaminants of concern at the Site.

Reference doses (RfDs) have been developed by U.S. EPA for indicating the potential for adverse health effects from exposure to chemicals exhibiting noncarcinogenic effects. RfDs, which are expressed in units of mg/kg-day, are estimates of the daily exposure to the human population (including sensitive subpopulations) that is likely to be without an appreciable risk of deleterious effects during a lifetime. RfDs are derived from human epidemiological studies or animal studies to which uncertainty factors help ensure that the RfDs will not underestimate the potential for adverse noncarcinogenic effects to occur. The reference doses for contaminants of concern at the Site are specified in Table 2.

4. Risk Characterization

Using the maximum levels of each contaminant detected in the groundwater for each respective calculation, the excess cancer risk and non-cancerous effects were calculated for current and future scenarios. Under current-use conditions, the groundwater data used was from monitoring wells located near and far downgradient from the Site. The cancer risk due to the ingestion of groundwater near downgradient is 2 X 10⁴.

The cancer risk due to the inhalation of VOCs from showering is 2 X 10⁻⁵. The hazard index for ingestion of near downgradient groundwater is 3, and far downgradient groundwater is 10. The higher hazard index for far downgradient groundwater (10) is the result of higher contaminant concentrations detected in far downgradient wells. Higher contaminant concentrations in far downgradient wells may possibly be due to downward vertical gradients of the plume. The hazard index numbers indicate that exposure to contaminants may produce harmful, non-cancerous effects.

Accordingly, under future-use conditions, it is assumed that residential housing would be developed around the Site. The groundwater data collected from on-property wells were used to calculate the risk for the future-use scenario. The cancer risk through the ingestion of groundwater in shallow wells is 2 X 10⁻³. The hazard index from shallow wells located on site is 6,000. U. S. EPA considers these risks unacceptable. Table 3 contains the cancer risk and hazard index for current and future cases.

TABLE 2 Hagen Farm Landfill Site ORAL TOXICITY CRITERIA FOR CHEMICALS OF POTENTIAL CONCERN

Chemical	Chronic Reference Dose (mg/kg - day) ⁻¹	Slope Factor (mg/kg - day)-1
Organic Chemicals		
Acetone		1.00E-01
Benzene	2.90E-02	
Benzoic Acid	2.702 02	4.00E+00
Benzyl alcohol		3.00E-01
2-Butanone (methyl ethyl ketone)		5.00E-02
Chlorobenzene		2.00E-02
Chloromethane	1.30E-02	
4,4'-DDE	3.40E-01	ļ
Di-n-octylphthalate		2.00E-02
1,4-Dichlorobenzene	2.40E-02	1.00E-01
1,1-Dichloroethene	6.00E-01	9.00E-03
1,2-Dichloroethene		2.00E-02
Dieldrin	1.60E+01	5.00E-05
Diethylphthalate		8.00E-01
2,4-Dimethylphenol		2.00E-02
Ethylbenzene		1.00E-01
4-Methylphenol (p-cresol)		5.00E-02
Naphthalene		4.00E-03
Phenol		6.00 E- 01
Tetrahydrofuran		2.00E-03
Toluene		2.00E-01
Vinyl Acetate		1.00E+00
Vinyl Chloride	1.90E+00	
Xylenes (total)		2.00E+00
Inorganic Chemicals		
Arsenic	1.80E+00	1.00E-03
Barium		7.00E-02
Copper		3.70E-02
Manganese		1.00E-01
Mercury		3.00E-04
Nickel		2.00E-02
Vanadium		7.00E-03
Zinc and compounds		2.00E-01

TABLE 3 Hagen Farm Landfill Site SUMMARY OF POTENTIAL HEALTH RISKS ASSOCIATED WITH CURRENT AND FUTURE LAND USE CONDITIONS

Exposure Pathway	Upper Bound Excess Lifetime Cancer Risk ^a	Hazard Index for Noncarcinogenic Effects ^b
Current Residents		
Ingestion of Groundwater (Off-property Shallow Wells)		
Downgradient - Near Downgradient - Far	2E-04	>1 (3) >1 (10)
Inhalation of Volatiles from Sowering with Groundwater (Off-Property Shallow Wells)		;
Downgradient - Near	2E-05	<1
Downgradient - Far	8E-07	<1
Future Residents		
Ingestion of Groundwater		
Hypothetical Resident on Property		•
(Shailow wells)	2E-03	>1 (6,000)
(Shallow wells - On Property Data)		>1 (30)
(Deep wells)	2E-05	>1 (300)
Inhalation of Volatiles from Showering with		ĺ
On-Site Groundwater		
Hyptothetical Resident		
(Shallow wells)	2E-04	>1 (300)
(Shallow wells - On Property Data)		≠1 ^c
(Deep wells)	5E-06	>1 (9)

^a The upper bound individual excess lifetime cancer risk represents the additional probability that an individual may develop cancer over a 70-year lifetime as a result of exposure conditions evaluated.

^b The hazard index indicates whether or not exposure to mixtures of noncarcinogenic chemicals may result in adverse health effects. A hazard index less than one indicates that adverse human health effects are unlikely to occur.

[°] When recalculated by target organ or effect, all hazard index values were less than one.

b. Environmental Risks

An ecological risk assessment was conducted to evaluate potential impacts on nonhuman receptors associated with the site. An evaluation of selected terrestrial plants and soil organisms (earthworms) to chemicals of potential concern indicated that neither plant nor earthworm populations would be adversely affected.

VII. DOCUMENTATION OF SIGNIFICANT CHANGES

No significant changes have been made since the May 1992 publication of the FS and Proposed Plan.

VIII. DESCRIPTION OF ALTERNATIVES

Based on the results of the RI and risk assessment, an FS was conducted to identify and evaluate a variety of alternatives for protecting human health and the environment from the contamination associated with the groundwater contamination at the Site. After identifying and screening potential remedial technologies for the Site, two alternatives were selected for further evaluation. The selection of these two alternatives from various remedial technologies was based on the screening process considering the remediation goal, the results of the treatability study, volume of groundwater to be treated, contaminant levels, and the merit of the technology. Each of the alternatives is evaluated using a set of nine criteria. These criteria reflect the goals of the Superfund program. They are used by U.S. EPA to compare the merits of each alternative. These criteria are explained in Section IX.

Descriptions of the two alternatives considered by U.S. EPA are provided below, including costs, estimated in terms of capital cost and annual operation and maintenance cost. Together, these dollar amounts are converted to net present worth. U.S. EPA's evaluation of each remedial alternative using the evaluation criteria is summarized in Section IX.

Due to the relatively low concentration levels of contaminants detected off-property and lack of information collected for the off-property aquifer, the groundwater contamination at the Site was separated into on- and off-property groundwater contamination. The terms "on-property" and "off-property" are defined in Section II. More studies will be conducted off-property as part of the RD/RA Phase to characterize the off-property aquifer and to gather other necessary information.

The alternatives considered for the GCOU are:

Alternative 1: No Action.

Alternative 2: Groundwater extraction and treatment;

Discharge of treated groundwater to the wetlands

or Yahara River.

A description of each of these alternatives follows:

Alternative 1: No Action

Under this alternative, the Site would be left in its present condition and no action would be taken to reduce the risk of exposure to contamination. U.S. EPA requires consideration of a no-action alternative to serve as a basis against which other remedial alternatives can be compared. Under this alternative, groundwater-quality monitoring of selected on-property, off-property, and all private wells located on and around the Site will be continued.

The capital cost of this alternative is approximately \$179,000, and annual Operation and Maintenance (O&M) is \$50,000. The 30-year present net worth (PNW) cost is \$1,025,000.

Alternative 2: Groundwater extraction and treatment;
Discharge of treated groundwater to the wetlands or Yahara River.

(a) Groundwater Extraction and Treatment

Under this alternative, on-property groundwater will be extracted and treated using an activated sludge biological system. The off-property groundwater will be extracted and treated using the treatment technology which will be selected during the Remedial Design (RD) stage. The off-property treatment technology will selected during the RD stage because additional information is needed concerning the off-property aquifer. The treated groundwater will be discharged into the wetlands or Yahara River. The treated on-property groundwater may also be reinjected to the on-property aquifer with nutrients and/or oxygen to enhance biodegradation. The private wells located around the Site will be monitored. It is anticipated that aquifer restoration under this alternative may require a 30 year period.

Groundwater extraction will be performed by a series of groundwater extraction wells placed at strategic locations downgradient of the source of contamination. The precise location, number, and depth of these wells will be established in the RD phase. Preliminary aquifer flow analysis indicates

that wells extracting 100 to 180 gallons per minute (GPM) should contain and significantly reduce the contamination within the plume.

The extracted groundwater from on-property will be treated using an activated sludge biological system. In a biological treatment process, the contaminants act as an energy source for biological microorganisms. If, over time, the contaminant concentrations become too low to support biological growth, additional materials (e.g., milk whey) may be added to maintain optimum biological activity for contaminant degradation. When influent contaminant concentrations in the biological process decrease to a level insufficient to support biological activity without large additions of substrate, a more cost-effective option may be to switch to a physical or chemical treatment process, such as Granular Activated Carbon (GAC). The biological system should remove up to 99 percent of the contaminants in the groundwater. Prior to the biological treatment, the extracted on-property groundwater would be passed through the pretreatment facility to remove metals and inorganic solids.

In addition, the treated on-property groundwater may be enhanced with nutrients and/or oxygen and reinjected into the aquifer to promote in-situ contaminant biodegradation in groundwater and saturated soils, potentially decreasing the time necessary for extraction and treatment. The reinjected water may also help flush additional contaminants from the aquifer. Preliminary groundwater flow analysis indicated that approximately 30 percent of the total on-property extraction volume will be treated to NR 140 Preventive Action Limits (PALs) by biological treatment and reinjected into the aquifer. Because the effectiveness of this enhancement is uncertain, full implementation should be preceded by a testing and evaluation phase to determine the feasibility of performing long-term insitu bioremediation treatment. A bench scale study would be implemented first to determine the effect of nutrients and oxygen on contaminated groundwater. If the bench scale study shows positive results, a pilot study would be conducted with the ultimate goal of enhancing the selected remedy with an insitu groundwater bioremediation system.

For the treatment of extracted off-property groundwater, the following five technologies will be evaluated:

Option 2A: Cascade Aeration Option 2B: Biological Treatment

Option 2C: Air Stripping

Option 2D: Granular Activated Carbon (GAC)
Option 2E: Ultraviolet (UV)-Chemical Oxidation

Option 2A: Cascade Aeration

The cascade aeration system utilizes a modified pipeline with an open channel gravity flow section in order to strip the VOCs in the groundwater. This flow section would create turbulence in the water and enhance air-water contact prior to discharge to the Yahara River. This open channel segment would promote the transfer of volatile contaminants to the air. It is expected that the cascade aeration system is not as efficient as the air stripping process evaluated in the treatability study, and would remove less than 40 percent of the THF in the off-property groundwater. Pretreatment for metals and inorganic solids would be necessary prior to cascade aeration. Since cascade aeration has a low removal rate for THF, the treated groundwater using cascade aeration will not be discharged into the wetlands.

Option 2B: Biological Treatment

Off-property groundwater would be combined with more highly contaminated groundwater from on site, pretreated to remove metals and inorganic solids, and then biologically treated to remove the organic compounds. If combined groundwater contamination concentrations from both on- and off-property become too low to support biological growth, additional substrate material may be added to maintain optimum biological activity for contaminant degradation.

Option 2C: Air Stripping

Off-property groundwater would first be pretreated to remove metals and inorganic solids, and then conveyed to a packed-tower air stripper which uses countercurrent aeration, in which influent water flows into the top of the tower and cascades through a packing media, while air is forced upward through the tower. This allows a transfer of contaminants in the liquid phase to the gas phase by providing a larger contact surface and void volume for phase transfer of the contaminants and a sufficient residence time for the transfer to occur. The air stripping could reduce THF contamination by up to 40 percent and remove other less soluble VOCs by greater amounts. The treated groundwater using air stripping will not be discharged to wetlands due to the low removal rate.

Option 2D: Granular Activated Carbon (GAC)

Off-property groundwater would first be pretreated to remove metals and inorganic solids, and then conveyed to the GAC bed, where contaminants are adsorbed on the carbon. When the capacity of the carbon is exhausted, the bed is taken out of service and the spent carbon either regenerated or disposed of in an off-site landfill to meet the Land Disposal Restriction requirements. Based on the treatability study, the GAC would

remove up to 99 percent of the contaminants in the groundwater. However, the main contaminant in the off-property groundwater, THF, is not readily adsorbable, and will require large quantities of GAC for complete adsorption.

Option 2E: Ultraviolet (UV)-Chemical Oxidation

Chemical oxidation and UV light would be used to destroy VOCs in the contaminated off-property groundwater. Chemical oxidation uses strong oxidizing agents to react and destroy organics in groundwater. UV light would be used in conjunction with the oxidizing agents (such as hydrogen peroxide and ozone) to improve the oxidation process efficiency. The treatability study for on-property groundwater indicated that data from vendors show that UV/peroxide oxidation with pre-filtration was able to remove THF concentrations as high as 57,000 ug/l. This technology should remove up to 99 percent of the contaminants from the extracted off-property groundwater. Consequently, this process will need to be preceded by an inorganics removal pretreatment process such as air oxidation/precipitation or pH adjustment to remove metals which could cause scaling on ultraviolet lamps.

(b) Selection of Off-Property Groundwater Treatment Technology

U.S. EPA, in consultation with WDNR, will select the off-property groundwater treatment technology from the five technologies described above. The selection of the technology will be based on design information including, but not limited to, an off-property pump test, off-property treatability study, and bio-assay test. U.S. EPA will consider the off-property aquifer characteristics, the surface water discharge limits for the contaminants of concern for discharge to the Yahara River, groundwater discharge limits for the contaminants of concern for discharge to wetlands, and the ability of these technologies to meet ARARs. After selection of the off-property groundwater treatment technology, the U.S. EPA will issue an explanation of significant differences (ESD) to inform the public of U.S. EPA's decision.

(c) Discharge of Treated Groundwater

The treated on- and off-property groundwater could be discharged to the Yahara River through an 11,000-foot force main water line which must, at some point, tunnel beneath the Chicago, Milwaukee, St. Paul, and Pacific Railroad line which lies between the Site and the Yahara River. The cascade aeration treatment system would replace a segment of the force main if that treatment system is selected for off-property groundwater. The treated groundwater could also be discharged into wetlands.

The discharge location will be determined after a Site specific evaluation including an evaluation of the impact of ARARs on the design of the groundwater extraction and treatment system and effluent discharge limits.

(d) Groundwater Cleanup and Discharge Standards

Groundwater will be extracted until the groundwater no longer attains or exceeds Wisconsin NR 140 PAL standards at the point of compliance and beyond. Consistent with the exemption criteria of NR 140.28, WAC, an alternative concentration limit (WACL) may be established if it is determined that it is not technically or economically feasible to achieve the PAL for a specific substance. The point of compliance shall be the waste management boundary.

Discharge of treated groundwater to the Yahara River will be required to comply with the requirements set forth in a WPDES permit, since discharge to the Yahara River would be considered an off-site discharge.

Discharge of treated groundwater into the wetlands via the drainage ditch near the southeast corner of the Site or directly to the wetlands will be required to meet the substantive requirements of a WPDES permit and shall comply with NR 140, PAL standards. In addition, the State of Wisconsin also has policies on protection of wetlands which shall be complied with for actions affecting wetlands including NR 1.95 and 103 Wis. Adm. Code. Impacts to the wetlands will be considered and minimized to the extent possible during the design phase of this remedial action as directed in Executive Order 11990.

(e) Air Emission Treatment

The emitted gases produced by waste water treatment system will be treated to meet State air-quality standards in accordance with the Clean Air Act (CAA) and NR 400 through 499, WAC.

(f) Sludge Management

All residue, sludge, and/or spent coagulants/agents from the treatment of groundwater shall be treated to meet the Land Disposal Restriction (LDR) standards for F003-F005 wastes prior to disposal in a Resource Conservation and Recovery Act (RCRA) landfill in accordance with the requirements of 40 CFR 268.41. Spent carbon will be regenerated or treated to meet the LDR requirements.

(q) Cost

Depending on the selection of off-property groundwater treatment options and the location of discharge of treated groundwater, the cost of this alternative will vary. The detailed cost information is contained in Table 4. The capital costs range from \$4,396,000 to \$6,288,000, annual O&M costs range from \$550,000 to \$1,027,000, and 30-year total PNW cost ranges from \$13,612,000 to \$24,163,000.

IX. SUMMARY OF THE COMPARATIVE ANALYSIS OF ALTERNATIVES

A detailed analysis was performed on the two alternatives using the nine evaluation criteria in order to select a groundwater control remedy. The following is a summary of the comparison of each alternative's strength and weakness with respect to the nine evaluation criteria. These nine criteria are:

- 1) Overall Protection of Human Health and the Environment
- 2) Compliance with Applicable or Relevant and Appropriate Requirements (ARARs)
- 3) Long-Term Effectiveness and Permanence
- 4) Reduction of Toxicity, Mobility, or Volume through Treatment
- 5) Short-Term Effectiveness
- 6) Implementability
- 7) Cost
- 8) State Acceptance
- 9) Community Acceptance

1. Overall Protection of Human Health and the Environment

Alternative 1, No Action, will not provide adequate protection from risks associated with contaminated groundwater. The private wells located downgradient of the Site might be exposed in the future. Therefore, it will not be discussed any further, since it is not protective and, thus, not an acceptable alternative. Additional contaminant loading into the aquifer will, however, be reduced by implementation of the cap and ISVE system determined in the ROD of the SCOU.

Alternative 2 provides protection of human health and the environment because it includes an extraction and treatment system to remove and treat the contaminated groundwater from the aquifer.

2. Compliance with ARARs

Alternative 2 would comply with all applicable or relevant and appropriate federal and state environmental laws.

TABLE 4
Summary of Cost Estimates for
Hagen Farm GCOU Feasibility Study Alternatives

Alternatve 1: No Action				
	Capital Costs Annual Operating Costs Total Present Net Worth	\$ 179,000 \$ 50,000 \$ 1,025,000		
Alternative 2: Extra	action, Treatment, and Discharge			
Alternative		Discharge to Yahara River	Discharge to <u>Wetlands</u>	
Option 2A:	Capital Costs	\$ 4,396,000		
Activated Sludge	Annual Operating Costs	\$ 550,000		
Cascade Aeration	Total Present Net Worth	\$13,612,000	N/A	
Option 2B:	Capital Costs	5,217,000	4,413,000	
Activated Sludge	Annual Operating Costs	69 9,000	665,000	
	Total Present Net Worth	16,943,000	15,589,000	
Option 2C:	Capital Costa	5,816,000		
Activated Sludge	Annual Operating Costs	765,000		
Air-Stripping	Total Present Net Worth	18,645,000	N/A	
Option 2D:	Capital Costs	5.986,000	5,181,000	
Activated Sludge	Annual Operating Costs	805,000	770,000	
GAC	Total Present Net Worth	19,491,000	18,119,000	
Option 2E:	Capital Costs	6,288,000	5,482,000	
Activated Sludge	Annual Operating Costs	1,062,000	1,027,000	
UV-Chem Ox	Total Present Net Worth	24,163,000	22,790,000	

Note:

- 1. Present net worth assumes 30 years of operation, 9% discount rate, and a 5% inflation rate.
- 2. N/A indicates not applicable for the alternative or option.
- 3. The Alternative 2 costs include in-situ bioremediation.

The major groundwater ARARs include the Federal Safe Drinking Water Act (SDWA) and State Groundwater Quality Standards, NR 140, WAC.

The major surface water discharge ARARs include Chapter 147 Wisconsin Statutes, NR 102, 104, 105, 106, 108, 200, 207, 219, and 220 of WAC.

The major wetland discharge ARARs include NR 1.95, 103, and 140 (PAL Standards) of WAC, and the substantive requirements of a WPDES permit (Chapter 147 Wisconsin Statutes, NR 102, 104, 105, 106, 108, 200, 207, 219, and 220 of WAC).

The groundwater wells for the alternatives will be constructed according to the standards listed in NR 112 and 141, WAC. Wastewater treatment facility standards will be followed according to NR 108, WAC.

Water used for in-situ bioremediation will be treated to achieve NR 140, PALs prior to re-injection into the aquifer. Any proposal to re-inject treated groundwater enhanced with nutrients and/or oxygen must comply with the substantive requirements of Ch. NR 112, WAC. Feasibility and evaluation testing of in-situ bioremediation should be evaluated during implementation of the remedial action.

NR 445, Control of Hazardous Pollutants, is an ARAR for Alternative 2. Off-gases generated from the treatment process should be treated in order to meet NR 445 emission limit requirements. In general, NR 400 to 499, WAC (Air Quality Management) is an ARAR for the emission of off-gas.

A more complete list of ARARs is included in Section XI.

3. Long-term Effectiveness and Permanence

Cascade aeration and air stripping may require consideration of the residual risks due to potential exposure to the community. This exposure may occur through inhalation of volatilized contaminants from the aeration channel and air stripper, respectively, if they exceed NR 445 standards. Alternative 2 also has a risk component due to the residual contamination in the water being discharged to the Yahara River. The risk due to the implementation of air stripping may be slightly less than from cascade aeration because the air stripper is expected to remove more contaminants than the cascade aeration system.

Potential risks exist for all treatment options due to the transport, storage, and disposal of pretreatment and treatment process residuals which may be hazardous waste. The level of risk is approximately proportional to the quantities of waste generated. The GAC has greater potential risk because it

generates residuals from activated carbon treatment process. Biological treatment, air stripping, and UV-chemical oxidation generate slightly less treatment process residuals. Cascade aeration generates the smallest volume of potentially hazardous waste because there might be no pretreatment process for the water, and the cascade aeration treatment process generates no residuals.

There is no difference between the effectiveness of the institutional controls or the proposed groundwater monitoring for any of the treatment options in Alternative 2.

The surface water discharge limits, which will be established by U.S. EPA in consultation with WDNR, will determine whether the contaminant removal levels for off-property groundwater treatment options, cascade aeration and air stripping, are adequate. Treatment options such as biological treatment, GAC, and UV-chemical oxidation should be adequate for treatment to the required discharge limits.

4. Reduction in Toxicity, Mobility, or Volume

Alternative 2 uses a groundwater well extraction network to remove contaminated groundwater from the ground and a biological treatment process to remove organics from the extracted on-property groundwater. Pretreatment would be included and would likely consist of a precipitation process to remove inert solids and metals.

The amount of hazardous materials extracted from the groundwater aquifer is the same, regardless of which treatment option in Alternative 2 is selected.

The biological treatment system proposed to treat extracted groundwater from on-property is expected to remove up to 99 percent of the contaminants in the groundwater. Based upon the treatability study, the cascade aeration system proposed for off-property groundwater is expected to be less efficient than air stripping. Cascade aeration is expected to remove less than 40 percent of the THF in the off-property groundwater. It is also expected to remove the less-soluble VOCs (e.g., vinyl chloride) in the contaminated off-property groundwater. The biological treatment is expected to remove up to 99 percent of the contaminants in the off-property groundwater. The air stripper system is expected to remove up to 40 percent of the THF and provide even greater reduction of other less-soluble VOCs in the contaminated groundwater. The GAC treatment system and the UV-chemical oxidation system is expected to remove up to 99 percent of the contaminants from the extracted off-property groundwater. Removal efficiencies are based upon the treatability study, which was conducted using on-property contaminant concentrations. Actual removal efficiencies are

dependent upon field conditions, and would need to be further evaluated in the RD phase.

Reduction of hazardous materials through in-situ bioremediation cannot be estimated at this time. Evaluations of the effectiveness of in-situ bioremediation will be made in the insitu bioremediation pilot testing phase conducted when the GCOU extraction system has equilibrated. Prior to conducting the insitu bioremedial pilot testing phase, groundwater injection should be performed and the system allowed to reach equilibrium. An evaluation to assess the incremental benefit attributable to reinjection without the addition of nutrients and/or oxygen can then be made.

Alternative 2 will reduce the toxicity and volume of the contamination in the aquifer, and limit additional contaminant migration.

In-situ bioremediation may increase the rate of in-situ biodegradation. This potential for increased biodegradation will be evaluated by feasibility testing in the RA implementation phase.

The extraction of contaminated groundwater and subsequent treatment for all treatment options is irreversible. In-situ biodegradation reactions for the treatment of organic compounds is also irreversible.

In-situ bioremediation has the potential to reduce groundwater concentrations below those achievable by extraction alone. However, some residual contaminants are expected to remain under any extraction or in-situ treatment method.

The pretreatment system and biological treatment system for onproperty groundwater treatment will produce an estimated 550 pounds per day of metal and inorganic residuals, which may be hazardous. The biological treatment system is expected to produce an estimated 170 pounds per day of potentially hazardous sludges due to inclusion of the off-property groundwater in the treatment process. The air stripping system, GAC, and UVchemical oxidation are each expected to produce an additional estimated 200 pounds per day of potentially hazardous sludges. Sludge generation rates are based on sludge generation data gathered in the treatability study. GAC is also estimated to produce 75 pounds per day of spent carbon from the GAC process.

All Alternative 2 options will reduce the inherent hazards posed by the groundwater contamination at the Site to risk levels considered protective of human health and the environment through groundwater extraction and treatment.

Activated sludge biological treatment would utilize the ability of certain bacteria to break down organic compounds into carbon dioxide and water. Cascade aeration and air stripping involve the transfer of volatile contaminants to the air. contaminants in the off-gas could be adsorbed in the carbon and treated if spent carbon is regenerated. Regeneration usually involves heating the carbon to very high temperature in a kiln to desorb the contaminants. The desorbed contaminants can then be incinerated. GAC utilizes the adsorption process in which molecules in an aqueous solution adhere to the surface of a The contaminants which adhered in the surface of a solid. carbon bed can be treated through a regeneration process. oxidation involves the use of UV radiation in conjunction with one or more oxidizing agents, usually ozone or hydrogen peroxide, to chemically destroy organic contaminants. Ozone and hydrogen peroxide are both strong oxidizing agents that can chemically break down organic compounds. In the presence of UV radiation, the effectiveness of these oxidizing agents is dramatically increased.

5. Short-term Effectiveness

Risks to the community from Alternative 2 are due to the offsite transport of sludges and treatment residues generated by the pretreatment and/or treatment processes for each treatment option. The level of risk is approximately proportional to the quantities of wastes generated.

Alternative 2 should cause no additional risks to workers beyond normal risks associated with construction, provided that a Health and Safety Plan is developed and followed.

The disturbance of the wetlands due to monitoring and extraction well construction could occur during the construction of Alternative 2, depending upon well locations. Wetlands may also be damaged during winter months by ice buildup from continual water discharges to wetlands from the treatment of the biological system, GAC, or UV-chemical oxidation. Such damage should not occur if preventative measures such as intermittent pumping or engineered control systems (e.g., stilling basins) are employed. Such damage could be avoided entirely if treated wastewater is discharged to the Yahara River instead of the wetlands. These potential impacts to the wetlands will be evaluated during the RD phase and will be minimized.

For Alternative 2, the time required to achieve the RA objectives is limited by the extraction technology, as described in Alternative 2. Remediation times are described in terms of advective flushing times. The effects of retardation and dispersion are not accounted for in the groundwater remediation time estimates. Advection flushing time is between 10 and 15 years for Alternative 2. The addition of in-situ bioremediation

may decrease the remediation time to between 5 and 10 years. Actual cleanup time will likely be substantially longer due to the effects of retardation and dispersion, although these effects may be offset by the degradation stimulated by in-situ bioremediation.

6. <u>Implementability</u>

The extraction well network for Alternative 2 is readily implementable.

The technologies required to implement the treatment system for Alternative 2 and its off-site treatment option are readily available, although the biological treatment system requires a start-up period before it reaches the optimum operating efficiency. If intermittent pumping is required to reduce impacts to the wetlands, operation of a biological treatment system will be difficult to control. However, intermittent pumping of individual wells should be possible without causing operational problems.

A testing and evaluation period is needed to determine if insitu bioremediation is technically feasible before full-scale implementation. The biological treatment system which reduces contaminant levels to required discharge levels may require modifications as groundwater contaminant levels decrease over time. All off-property treatment options may require a pilot scale test to establish operation parameters of treatment technology.

Discharge standards to the Yahara River need to be determined before it will be known whether treatment options, such as cascade aeration or air stripping, meet surface water discharge standards.

Alternative 2 requires additional materials and services. However, these materials are expected to be readily available. If shown to be feasible, in-situ bioremediation utilizes materials and services available from the consulting and environmental services communities.

7. Cost

The cost of each alternative is summarized in Table 4.

8. State Acceptance

The WDNR concurs with the selection of Alternative 2 on the condition that the WDNR determines, at the time the proposed treatment design is finalized, that the effluent discharge limits and discharge location (including any reinjection of enhanced groundwater which is proposed) are acceptable to the

WDNR and are in compliance with the effluent discharge limit requirements of Chapters NR 102, 104, 105, 106, 108, 200, 207, 219 and 220, WAC, Ch NR 140, WAC, PAL Standards, the wetlands protection in Ch NR 103 WAC, and the applicable air quality standards in Chs NR 400 to 499, WAC.

9. Community Acceptance

The specific comments received and U.S. EPA's responses are outlined in the attached Responsiveness Summary.

X THE SELECTED REMEDY

As provided in CERCLA and the NCP, and based upon the evaluation of the RI/FS and the nine criteria, U.S. EPA, in consultation with the WDNR, has selected Alternative 2 as the groundwater control remedial action at the Hagen Farm Site.

- Institutional controls would include on-property land and on- and off-property groundwater use restrictions in the form of existing deed restrictions to the extent necessary to implement and protect the remedy, and to safeguard human health and the environment during implementation of the remedy. The cooperation of local agencies would be required to limit future off-property use of groundwater if the Respondents are unable to obtain deed restrictions from affected property owners. A fence shall be installed around the treatment facility system in order to prevent public access.
- Additional monitoring will be conducted in the selected onand off-property monitoring wells and all of the private wells located around the Site, including but not limited to, the wells located on the properties of Fosdohl, Lee, Van Deusen, Sundby, Sundby Sand and Gravel, K-Way Insulation, Gullickson, Quam, Stoughton Conservation Club, Sagmoen, and Gjertson.
- Extracted groundwater from on- and off-property would be pretreated for the removal of metals and inorganic solids.
- On-property groundwater will be extracted until the groundwater at the waste management boundary and beyond (area of attainment) no longer attains or exceeds Wisconsin NR 140 PAL standards, and treated using an activated sludge biological system. All residue and/or sludge shall be treated as appropriate to meet the LDR standards for F003-F005 wastes and shall be placed in a RCRA landfill in accordance with the requirement of 40 CFR 268.41.

- off-property groundwater will be extracted until the groundwater within the area of attainment no longer attains or exceeds Wisconsin NR 140 PAL standards and treated using an appropriate treatment technology. Treatment technologies such as cascade aeration, activated sludge, air stripping, GAC, or UV-oxidation shall be evaluated during the RD stage. Based on the off-property pump test, bioassay test, BAT requirements, surface water discharge limits, and other related factors, the technology will be selected for off-property groundwater treatment. The emitted gases will be treated to meet State air-quality standards of NR 445, WAC. All residue, sludge, and/or spent coagulants shall be treated as appropriate to meet the LDR standards for F003-F005 wastes and shall be placed in a RCRA landfill in accordance with the requirement of 40 CFR 268.41. The spent carbon could be regenerated or treated to meet LDR requirements prior to land disposal.
- A bench scale study will be conducted to examine the feasibility of injecting the treated on-property groundwater into the on-property aquifer in order to enhance in-situ bioremediation. Nutrients and/or oxygen would be added in order to promote the natural microbial degradation of organic compounds. The study will be designed to determine the optimum amounts of nutrients to be added to the aquifer, and the amount of groundwater to be injected. If determined to be feasible, a pilot study would be implemented with the ultimate goal of enhancing the selected remedy with a full scale in-situ groundwater bioremediation system. The discharge limit of NR 140, PAL standards shall be met in order to inject treated groundwater into the on-property aquifer.
- The treated groundwater will be discharged to the Yahara River or nearby wetlands. Discharge of treated groundwater into the wetlands via the drainage ditch near the southeast corner of the Site or directly to the wetlands should meet the substantive requirements of a WPDES permit and shall comply with NR 140, PAL standards. In addition, the State of Wisconsin also has policies on protection of wetlands which shall be complied with for actions affecting wetlands including NR 1.95 and 103, Wis. Adm. Code. Impacts to the wetlands will be considered and minimized to the extent possible during the design phase of this remedial action as directed in Executive Order 11990. Discharge of treated groundwater to the Yahara River will be required to comply with the requirements set forth in a WPDES permit, since discharge to the Yahara River would be considered an offsite discharge.

XI. STATUTORY DETERMINATIONS

The selected remedy must satisfy the requirements of Section 121 of CERCLA to:

- a. protect human health and environment;
- b. comply with ARARs;
- c. be cost effective;
- d. utilize permanent solutions and alternate treatment technologies to the maximum extent practicable; and,
- e. satisfy the preference for treatment as a principal element of the remedy or document in the ROD why the preference for treatment was not satisfied.

The implementation of Alternative 2 at the Site satisfies the requirements of CERCLA as detailed below:

a. Protection of Human Health and the Environment

This selected remedy will provide adequate protection of human health and the environment through treatment.

Risk posed by groundwater contamination will be reduced and controlled by the operation of a groundwater extraction and treatment system. Access restrictions will prevent direct contact with contaminated groundwater until groundwater cleanup standards are met.

No unacceptable short-term risks will be caused by implementation of the remedy. Standard safety programs, such as fencing, use of protective equipment, monitoring, and off-gas treatment, should mitigate any short-term risks. Short-term risks include exposure of site workers and the community to VOCs, and to noise nuisance during implementation of the groundwater remedy. Ambient air monitoring would be conducted and appropriate safety measures would be taken if contaminants were emitted.

b. <u>Compliance with ARARs</u>

The selected remedy complies with all Federal and State environmental requirements that are legally applicable or relevant and appropriate. The major Federal and State ARARs for the selected remedial alternative for the GCOU are listed below.

A) Federal ARARs

i. Groundwater

Relevant and appropriate requirements for groundwater include primary drinking water standards established by the federal SDWA.

Several contaminants of concern identified at the Site have Maximum Contaminants Level (MCLs), proposed MCLs and/or Maximum Contaminant Level Goals (MCLGs). MCLs are relevant and appropriate to circumstances at the Site, since the aquifers are current and potential sources of drinking water. MCLGs are relevant and appropriate when the standard is set at a level greater than zero (for non-carcinogen).

The NCP 40 C.F.R. 300 et seg. provides that groundwater cleanup standards should generally be attained throughout the contaminant plume or at and beyond the edge of the waste management area when waste is left in place. At the Hagen Farm Site, groundwater quality Standards shall be attained at and beyond the edge of the waste management area (i.e., at the edge of the landfill cap) since waste has been left in place. This is considered the area of attainment.

ii. Surface Water Discharge

Surface water quality standards for the protection of human health and aquatic life were developed under Section 304 of the Clean Water Act (CWA). The Federal Ambient Water Quality Criteria (AWQC) are nonenforceable guidelines that set pollutant concentration limits to protect surface waters that are applicable to point source discharges, such as from industrial or municipal wastewater streams.

National Pollutant Discharge Elimination (40 CFR Part 125); includes best available technology.

iii Wetlands Discharge

Executive Order 11990, 40 CFR 6.302 (a) - Protection of Wetlands - is applicable for this site if the discharge of treated groundwater is to the wetlands.

iv. Sludges

All sludges, residues, spent carbon, and/or spent coagulants produced from groundwater and off-gas treatment will be treated to LDR standards for F003-F005 waste prior to disposal at a RCRA landfill in accordance with the requirement of 40 CFR 268.41. If testing determines that waste sludge generated from the activated sludge

biological system is not hazardous, the waste sludge could be disposed of by on-Site landspreading or off-Site landfilling. Residues such as spent carbon from the treatment of groundwater which are regenerated must be treated in a unit in compliance with 40 CFR Part 264 Subpart X. Federal ARAR 40 CFR Part 261 - Land Disposal Restrictions shall also be complied with.

The sludge is not expected to contain metals at concentrations above characteristic levels. If, after testing by the Toxicity Characteristic Leaching Procedure (TCLP), it is determined that the sludge is characteristic for metals, it will be treated to render it non hazardous.

v. Air Emissions

National Primary and Secondary Ambient Air Quality Standards (40 CFR Part 50)

National Emissions Standards for Hazardous Air Pollutants (40 CFR Part 61)

B) State ARARs

i. Groundwater

is authorized State of Wisconsin administer the implementation of the Federal SDWA. The State has also promulgated groundwater quality standards in NR 140 Wis. Adm. Code, which, according to WDNR, is being consistently applied to all facilities, practices, and activities which are regulated by WDNR and which may affect groundwater quality in the State. Chapter 160, Wis. Stats., directs WDNR to take action to prevent the continuing release of contaminants at levels exceeding standards at the point of standards application (point of compliance). PALs and Enforcement Standards (ESs), have been promulgated in NR 140, Wis. Adm. Code. PALs are the groundwater cleanup standards under NR 140. PALs are generally more stringent than corresponding Federal standards and, therefore, are ARARs for the Hagen Farm Site.

Consistent with the exemption criteria of NR 140.28, Wis. Adm. Code, U.S. EPA may establish a Wisconsin Alternative Concentration Limit (WACL), if, based on Site-specific monitoring data

gathered before and after implementation of the selected groundwater remedy, U.S. EPA determines that it is not technically and economically feasible to achieve the PALs for a specific substance. Except where the background concentration of a compound exceeds the ES, and consistent with the criteria in NR 140. 28(4)(B), the WACL that is established may not exceed the ES for that compound.

The implementation of the selected remedy at the Site will be in compliance with NR 140, Wis. Adm. Code, in that PALs will be met unless WACLs are established pursuant to the criteria in NR 140.28, Wis. Adm. Code, in which case the WACLs will be met. These standards will be met in accordance with the NCP at and beyond the edge of the waste management area.

Groundwater Monitoring and Recovery Well requirements include NR 112, NR 141, NR 508, Wis. Adm. Code. Groundwater monitoring wells will be installed in accordance with NR 141, Wis. Adm. Code. Extraction and injection wells will be installed and operated in accordance with Ch. NR 112, Wis. Adm. Code.

Wastewater treatment facility will followed according to NR 108, WAC.

In order to reinject the treated groundwater into the on-property aquifer PALs under NR 140, WAC shall be achieved.

ii. Surface Water Discharge

A WPDES permit must be obtained before treated groundwater can be discharged to the Yahara River. Discharge to the Yahara River would be considered an off-site discharge.

The substantive requirements of WPDES for discharge of wastewater (treated groundwater) to the land and/or surface waters; effluent limits; discharge permits; sampling/testing methods is regulated by Ch. 147, Statutes - Wastewater Management Programs and Chs. NR 102, 104, 105, 106, 108, 200, 207, 219, and 220, WAC Surface Water Discharge Regulations (WPDES). These requirements are all applicable to the discharge of treated groundwater to the Yahara River. Ch. NR 220, WAC, requires that the effluent limits be

based on the application of best available technology (BAT) prior to discharge. The State has promulgated Wisconsin Water Quality Standards and Criteria (WWQC) under Chapters NR 102 and 105, WAC, and the procedures for calculating the toxic effluent limits under Ch. NR 106, WAC, based on the Federal AWQC developed by U.S. EPA. NR 102, 104 and 207 WAC also apply in determining water quality based limits.

iii Wetlands Discharge

Discharge of treated groundwater to the on-site ditch or adjacent to the wetlands should meet the substantive requirements of a WPDES permit and shall comply with Ch. NR 140, PAL standards. In addition, Ch. NR 1.95, WAC - Wetlands Preservation, Protection, and Management and Ch. NR. 103 - Water Quality Standards for Wetlands are applicable for this site if treated groundwater is discharged to the wetlands.

vi. Air Emissions

The emitted gases produced by waste water treatment system(s) will be treated to meet State air-quality standards in accordance with the Clean Air Act (CAA) and NR 400 through 499, WAC.

v. Miscellaneous State ARARs

- Discharge structures or other structures in a navigable water (Chapter 30, Wis. Adm. Code)
- Ch. NR 27, WAC, the State Endangered and Threatened Species Act and Ch. NR 29, WAC, the State Fish and Game Act are State endangered resource laws which protect against the "taking" or harming of endangered or threatened wildlife resources in the area. These would be applicable to the remedial action in that the poisoning of endangered or threatened species by site contaminants could be considered by the WDNR to be a "taking".

C) "To be Considered" Requirements

CERCLA Off-site Policy. (May 12, 1986), Revised November 13, 1987, OSWER DIR. 9834.11.

"Interim Policy for Promoting the In-State and On-Site Management of Hazardous Wastes in the State of Wisconsin"

provides a prioritization outline for the treatment and disposal of hazardous wastes and is "to-be-considered" for the site. If out-of-state treatment and/or disposal for the generated sludges is determined, the written documentation of how the waste management strategy and the eight evaluation criteria were applied shall be submitted to the WDNR for review and approval.

C. Cost Effectiveness

Cost effectiveness compares the effectiveness of an alternative in proportion to its cost of providing environmental benefits. Table 4 lists the costs associated with the implementation of the remedies.

The selected remedy is cost effective because it provides a high degree of overall effectiveness proportional to its costs. The estimated cost of the selected remedy is comparable with the other alternatives and assures a high degree of certainty that the remedy will be effective in the long-term due to the significant reduction of the toxicity of the contaminants in groundwater.

D. <u>Utilization of Permanent Solutions and Alternative</u> <u>Treatment Technologies or Resource Recovery Technologies to</u> <u>the Maximum Extent Practicable</u>

U.S. EPA believes that the selected remedy represents the maximum extent to which permanent solutions and treatment technologies can be utilized in a cost-effective manner for the RA at the Site. Treatment of contaminated groundwater will significantly reduce the hazards posed by the contaminated groundwater at the Site. The groundwater will be restored to the acceptable level to protect public health and the environment. U.S. EPA has determined that the selected remedy provides the best balance of tradeoffs in terms of long-term effectiveness and permanence, reduction of toxicity, mobility or volume through treatment, short-term effectiveness, implementability, cost, and State and community acceptance.

E. Preference for Treatment as a Principal Element

The selected remedy for the Site satisfies the statutory preference for treatment as a principal element through treatment of the contaminants in the groundwater. Treatment of the on-property groundwater contaminants using an activated biological sludge system will result in a significant reduction of contaminants in the groundwater. Treatment of the off-property contaminants using the technology selected during the RD stage will result in a significant reduction of contaminant toxicity in the off-property groundwater.

RESPONSIVENESS SUMMARY FOR THE RECORD OF DECISION FOR THE HAGEN FARM GROUNDWATER CONTROL OPERABLE UNIT

The United States Environmental Protection Agency (U.S. EPA) held a public comment period from June 1 through July 31, 1992, for interested parties to comment on the Proposed Plan for remediating contamination problems in the Groundwater Control Operable Unit ("GCOU") at the Hagen Farm Site (the "Site") in Dunkirk Township, Wisconsin. Comments were also taken on the documents in the administrative record, including the Remedial Investigation/ Feasibility Study (RI/FS) for the GCOU. The required public meeting on June 11, 1992, focused on the results of the GCOU FS and the U.S. EPA recommended alternative as presented in the Proposed Plan fact sheet. The public comment period was held in accordance with Section 117 of the Comprehensive Environmental Response, Compensation and Liability Act of 1980 (CERCLA) as amended.

The purpose of the Responsiveness Summary is to document U.S. EPA's responses, in consultation with Wisconsin Department of Natural Resources (WDNR), to comments received during the public comment period and public meeting. These comments were considered prior to selection of the final remedy for the GCOU at the Site, which is detailed in the Record of Decision (ROD).

BACKGROUND ON COMMUNITY INVOLVEMENT

U.S. EPA is responsible for conducting community relations program for this Site. A Community Relations Plan (CRP) was established by U.S. EPA for the Site in July 1988. It established a process to develop two-way flow of project information between local officials, concerned citizens, the media, WDNR and U.S. EPA. Two information repositories were established in the community -- Stoughton City Library, and Klongland Realty. Several different press releases and fact sheets were issued to announce field activities and findings of the RI and FS activities. A public meeting was held on July 14, 1988, at the start of the RI/FS to explain the investigation that was about to begin. Another public meeting to present the findings of the RI/FS and the Proposed Plan for the GCOU was held on June 11, 1992. Community relations activities are summarized in the ROD.

PUBLIC MEETING

The public meeting on the Proposed Plan for the Hagen Farm GCOU was held at 7:00 p.m. on June 11, 1992, at the Dunkirk Town Hall, County Trunk Highway N near Stoughton, Wisconsin. Approximately 15 persons attended, including local residents and representatives of the PRPs. Representatives of U.S. EPA and the WDNR presented information concerning the RI, the FS, and the Proposed Plan and responded to questions from individuals attending the meeting. Oral public comments were accepted during the meeting. A transcript of that meeting including the oral public comments, was prepared by a court reporter in attendance. Copies of the transcript are available at the two Site information repositories. No oral comments were received from the public during the public meeting.

PUBLIC COMMENT AND AGENCY RESPONSE

The following presents comments received from Waste Management of Wisconsin (WMWI) during the public comment period, and U.S. EPA's responses to those comments. WMWI is one of two Potentially Responsible Parties (PRPs). No other comments were received from the general public.

The comments from WMWI were in the form of correspondence submitted to U.S. EPA during the public comment period. U.S. EPA summarized each issue raised by WMWI and, where appropriate, information and statements presented by WMWI with the comments to support the issue. The original unsummarized correspondence submitted by WMWI can be found in the Administrative Record.

COMMENTS:

WMWI comments that the requirement for immediate implementation of a groundwater pump and treat system is not being applied consistently throughout the State of Wisconsin as well as throughout Region V. WMWI asserts that they should not be subjected to a higher standard of remediation than municipally owned or operated NPL sites, such as the Stoughton City Landfill. The ROD and subsequent Scope of Work (SOW) for the RD/RA phase should parallel the Stoughton City ROD's approach. Specifically, technical decisions should be put on hold for source area groundwater until the questions on the downgradient contaminant plume can be fully characterized.

In addition, WMWI comments that the timing of the implementation of pump and treat systems are being applied on an **ad hoc** basis. WMWI feels this is arbitrary and capricious and is inconsistent with the NCP. WMWI asserts that the EPA and WDNR should reevaluate the requirement for immediate groundwater extraction and treatment system at the Hagen Farm Site.

SUPPORTING STATEMENTS:

Stoughton City Landfill has similar contaminants to Hagen Farm and has significantly more potential receptors, but the Stoughton City Landfill ROD allows a grace period of 12 months after effective date of ROD to establish if pump and treat (P&T) is necessary. P&T will be necessary at Stoughton City Landfill if any monitoring well indicates the attainment or exceedance of an Enforcement Standard (ES). WMWI feels that U.S. EPA and WDNR have based their decision to implement a "contingency" ROD based on economical analysis of incremental risk reduction. WMWI states that the approach applied at Stoughton City Landfill is similar to that proposed by WMWI in the submittal of the Hagen Farm Draft Feasibility Study. WMWI feels that approving an approach similar to the Stoughton City Landfill, such as that proposed in the Draft FS, U.S. EPA could maintain consistency in their approach to the requirement for implementation of groundwater extraction and treatment systems. In addition, deferral of implementation of an immediate groundwater extraction and treatment system would allow an interim period to assess the effectiveness of the source control remedy and its impact on groundwater. During the interim period WMWI could also collect groundwater monitoring data that would allow for a more accurate model to predict contaminant levels and migration.

RESPONSE:

U.S. EPA does not believe it appropriate to postpone the implementation of a groundwater pump and treat system at the Hagen Farm Site. Although the commenter believes that by postponing the active remediation of the groundwater the U.S. EPA could study the impact of the source control remedy on the groundwater, and conduct studies and modeling on contaminant movement, U.S. EPA does not believe this to be an appropriate action. Although it is expected there will be a reduction in the future release of contaminants to the groundwater as the result of the implementation of source control measures, these measures are not adequate to clean up groundwater contamination to its beneficial use within a time frame that is reasonable. The groundwater contamination has migrated a significant distance from the site (approximately 3600 feet downgradient from the Site) and requires active implementation of a groundwater pump and treat system. The decision made by the U.S. EPA to require immediate implementation of a groundwater pump and treat system is fully consistent with CERCLA Section 104(a)(1) and as described in the NCP. First and foremost, Congress tasked U.S. EPA to respond to releases of hazardous contaminants in order to protect human health and the environment. U.S. EPA is not holding WMWI to a "higher standard of remediation than municipally owned or operated NPL sites." Rather, U.S. EPA is carrying out the requirements of the law to protect human health and the environment. The baseline risk assessment provides the basis for determining whether remedial action is necessary and justification for performing remedial actions to protect human

health and the environment. If contaminants of concern are listed in the baseline risk assessment as contributing to excess cancer risk outside an acceptable range of 1 x 10⁻⁴ to 1 x 10⁻⁶ or have a hazard index ratio greater than one, then remedial action is warranted. These criteria are provided in Section 300.430(e)(2) of the NCP. The Hagen Farm baseline risk assessment listed excess cancer risk as high as 2 x 10⁻³ and a hazard index ratio as high as 6,000. These values are outside the acceptable NCP values. Therefore, remedial action and compliance with pertinent ARARs under federal environmental laws or more stringent State environmental laws is necessary.

Based on information obtained during the RI, and on careful analysis of all remedial alternatives, U.S. EPA has concluded that the groundwater extraction and treatment component of the selected remedy has a high probability of success in terms of effectively withdrawing and removing contamination from the groundwater at the Hagen Farm Site. Therefore, U.S. EPA concludes that there is enough data to decide that groundwater extraction is necessary and appropriate for on- and off-property groundwater and that the information which is presented in the Final FS is appropriate.

Additional data collected from off-property groundwater during the RD Phase will be sufficient for a decision on a treatment technology for that contaminated groundwater. U.S. EPA believes that a delay in making a decision at the Hagen Farm Site would not be a prudent or responsible decision. A delay in the Agency's decision may result in further degradation of the aquifer's quality and may increase overall costs of a remedy. Seldom is the contamination problem less than what is discovered during the RI/FS. In fact, in most cases, based on Agency experience, the contamination problems become more complex and severe over time. The groundwater contamination at the Hagen Farm Site is very high, exceeding MCLs and/or State Enforcement Standards for organic compounds such as benzene, ethylbenzene, tetrahydrofuran, toluene, xylenes, and vinyl chloride. The highest exceedance was tetrahydrofuran, which was detected at a maximum concentration of 630,000 ug/l. Tetrahydrofuran alone exceeded the State Enforcement Standard of 50 ug/l by 12,600 times.

U.S. EPA does not believe that it is appropriate to apply the rationale used for selection of a groundwater remedy at the Stoughton Landfill in selecting the remedy for the Hagen Farm Site. The Stoughton City Landfill Site needs further characterization of the nature and extent of contaminated groundwater, both vertically and horizontally; hence the 12 month decision postponement. As stated above, enough information on the nature and extent of contamination at the Hagen Farm Site exists to support an Agency decision that groundwater extraction is an appropriate remedial technology. In addition, the two sites are not comparable.

Indeed, as WMWI admitted in trying to establish a similarity between the sites, the strongest statement that could be made was that the "...Hagen Farm Site, has contaminants similar to Stoughton City Landfill...". Although many sites may appear similar to the Hagen Farm Site, without a thorough examination of all of the site specific factors (i.e., geology, hydrogeology, and contaminants) it is difficult to determine an inconsistency in the application of environmental requirements.

Overall, WMWI's argument for a postponement of 12 months at the Hagen Farm Site is not based on the technical comparisons such as the type or concentration of contaminant present, but on consistency with another site. The only two technical arguments presented are: 1) the treatment option compatibility between off-and on-site (property) groundwater, and 2) the choice of a compliance point. Again, neither of these arguments are based technically on the type and concentration of contamination at the Hagen Farm Site, but are based on a question of consistency with the Stoughton City Landfill or other sites.

WMWI has charged that U.S. EPA based its decision at the Stoughton Landfill to implement a "contingency" ROD on an economical analysis of incremental risk reduction. This allegation is not true. On the contrary, U.S. EPA based its decision, in significant part, on the fact that the extent of groundwater contamination was not fully characterized. It was expected that the additional groundwater characterization activities would be completed within one year of ROD signature, thus the 12 month postponement of the extraction component of the remedy. In addition, WMWI stated that in the Stoughton ROD the U.S. EPA determined "treatment of the principle threat was not found to be practicable." However, this statement found in the Stoughton ROD refers to treatment of the actual waste material in the Stoughton Landfill, not the groundwater.

COMMENTS:

WMWI asserts that it is highly unlikely that the aquifer at the Hagen Farm Site can be restored to PALs or ESs, as established in NR 140.10, in a reasonable or even practicable time frame using groundwater extraction, even though groundwater extraction is the Best Available Technology (BAT) to mitigate the effects of groundwater contamination. WMWI states that at this time there exists no factual or credible evidence to support the belief or claim that the groundwater at the point of compliance selected by WDNR (the waste boundary) can be returned to its beneficial use as drinking water via the groundwater extraction remedial technology. Further, to require remediation of the aquifer to unachievable levels will only increase the length and cost of the cleanup, well beyond the point of diminishing returns. Therefore, WMWI asserts that U.S. EPA should issue an ARAR waiver for the applicability of the NR 140.10 and the Point of Compliance Applicability at the limits of the waste, based on the grounds of technical

impractibility pursuant to 40 CFR 330.430(f)(1)(ii)(c)(3), as authorized by 40 CFR 300.120. WMWI states that ACLs consistent with NR 140.28 and the protocol for establishing those levels should be developed during the preparation of the RD/RA SOW and subsequent Work Plans. WMWI wishes EPA to, at a minimum and in accordance with its own internal Memorandum on Groundwater treatment dated October 18, 1989, indicate in the ROD for the Hagen Farm Site that information gained during the implementation of the groundwater remedy may reveal that it is technically impractical to achieve health based concentration standards throughout the area of attainment.

SUPPORTING STATEMENTS:

WMWI cited a memorandum dated February 10, 1992 to William Reilly, U.S. EPA Administrator from Don Clay, Assistant Administrator, U.S. EPA, acknowledging the shortcomings of current groundwater remediation technology.

WMWI also cited recent studies which conclude that the effectiveness of extracting groundwater for the purposes of aquifer restoration is effective in containing contaminant migration and reducing contaminant mass, but is ineffective for restoring aquifer water quality within predictable time frames for highly contaminated sites.

WMWI listed site specific factors which could generally limit the effectiveness of groundwater extraction including:

- * Moderate adsorption of contaminants (e.g., 1,2-dichloroethene) which would take several times longer to purge than low adsorption constituents.
- * Numerous hydrogeologic heterogeneities that will tend to isolate some of the adsorbed contaminants from the extraction zone.
- * Ineffectiveness of pumping wells to capture immobilized contaminants in the vadose and capillary zones immediately beneath the landfill. The contaminants in the vadose and capillary zones can become a secondary source.
- * There has been no evidence of the presence of DNAPLs revealed during the course of the RI. However, it must be recognized that such evidence may not become readily apparent until the extraction system has been operating for an extended period of time.

RESPONSE:

Based on information obtained during the RI, and on careful analysis of all remedial alternatives, U.S. EPA concludes that the groundwater extraction and treatment component of the selected remedy has a high probability of success in terms of effectively

withdrawing and removing contamination from the groundwater at the Hagen Farm Site, especially THF. THF is completely miscible in water and is able to travel throughout the aquifer with negligible retardation effects. In addition, there is no evidence to demonstrate that a groundwater pump and treat system cannot restore the aquifer at the Hagen Farm Site to Wisconsin health based standards, even at the point of compliance. For these reasons, extraction and restoration of the plume in the aquifer is expected to be technically feasible. It follows then that an ARAR waiver for technical impractibility would not be appropriate. The technical impractibility waiver may be invoked when either of the following specific criteria are met:

- Engineering Feasibility. The current engineering methods necessary to construct and maintain an alternative that will meet the ARAR cannot reasonably be implemented.
- Reliability. The potential for the alternative to continue to be protective into the future is low, either because the continued reliability of technical and institutional controls is doubtful, or because of inordinate maintenance costs.

U.S. EPA does recognize the recent studies cited by WMWI concerning the effectiveness of groundwater extraction and a possible trend in the ineffectiveness of groundwater pump and treat technologies to restore aquifer water quality within predictable time frames.
U.S. EPA also recognizes a guidance memorandum, "Considerations in Ground Water Remediation at Superfund Sites" OSWER Directive 9355.4-03, dated October 18, 1989, assessing the effectiveness of nineteen operating groundwater extraction systems in achieving specified goals. The memorandum explained that ground water extraction was effective in containing plumes and achieving significant mass removal of contaminants. However, in many cases (not all), contaminant concentrations did not decrease linearly over time to reach desired remediation goals. After significant initial decreases, concentrations typically leveled off, often at concentrations higher than the cleanup levels. In addition, WMWI cites other studies which came to a similar conclusion. These cases are site-specific and may involve many variables quite different from the Hagen Farm Site. Not all cases demonstrated the inability to achieve specified goals. Again, there is no evidence to demonstrate that a groundwater pump and treat system cannot restore the aquifer at the Hagen Farm Site to health based standards. The ability to achieve cleanup goals at all points throughout the area of attainment, or plume, cannot be determined until the extraction system has been implemented, modified as necessary, and plume response monitored over time. This includes the area in the immediate vicinity of the contaminants' source, where concentrations are relatively high. Therefore, U.S. EPA continues to believe that clean-up standards are achievable until

the system, during operation, demonstrates otherwise. U.S. EPA has considered language in the internal Memorandum on Groundwater dated October 18, 1989, for the ROD. Therefore, as allowed for under NR 140, the U.S. EPA shall provide text in the ROD as follows:

Consistent with the exemption criteria of NR 140.28, Wis. Adm. Code, U.S. EPA may establish a Wisconsin Alternative Concentration Limit (WACL), if, based on Site-specific monitoring data gathered before and after implementation of the selected groundwater remedy, U.S. EPA determines that it is not technically and economically feasible to achieve the PALs for a specific substance. Except where the background concentration of a compound exceeds the ES, and consistent with the criteria in NR 140. 28 (4) (B), the ACL that is established may not exceed the ES for that compound.

U.S. EPA disagrees that the protocol should be established during the SOW preparation.

WMWI is concerned that moderate adsorption of contaminants and numerous hydrogeologic heterogeneities could limit effectiveness of groundwater extraction. The site specific factors presented by WMWI do not provide strong enough rationale to support a decision to not implement a groundwater pump and treat system or for an ARAR waiver based on technical impracticability. To begin with, U.S. EPA disagrees with WMWI's interpretation of the moderate adsorption of contaminants at the Hagen Farm Site. The RI The describes the aquifer material as a sand and gravel matrix. potential for attenuation/adsorption of organic contaminants within a sand and gravel deposit is low. Sand and gravels typically have low organic matter content which is not conducive to organic compound adsorption within the soil/water matrix. In addition, the the on-property groundwater organic and inorganic compounds of potential concern are ranked as relatively soluble in water and mobile, with the exception of BETX compounds. The primary off-property contaminant of potential concern is THF. THF is completely miscible in water and is able to travel throughout the aquifer with negligible retardation effects. Due to the high mobility of the contaminants at the Hagen Farm Site, the potential for contaminant migration in groundwater appears to be relatively Therefore, groundwater contamination is expected to be extracted relatively efficiently. BTEX compounds are expected to be less mobile than other compounds at the Site, but the effects of attenuation will remain uncertain until the groundwater pump and treat system is in operation. The specific example WMWI cited as a moderately adsorbed constituent was 1,2-dichloroethene. U.S. EPA disagrees with this characterization. 1,2-dichloroethene has organic carbon (K_{oc}) and octanol water (K_{ow}) distribution coefficients of 59 and 3.02 respectively, and a solubility of 6300 mg/l at 25°C. Compounds with K_{∞} values ranging from 50 to 150 and

K_{ow} values less than 5 are considered mobile to very mobile and have a low degree of adsorption (Dragun, 1988). A compound with a solubility of 6300 mg/l in general is considered very soluble. Effects from any heterogeneities at the site have yet to be determined. If heterogeneities factors do limit the effectiveness of groundwater extraction, their significance can only be determined during the actual operation of the pump and treat system.

wmwI is concerned that pumping wells may be ineffective in capturing immobilized contaminants in the vadose and capillary zones immediately beneath the landfill. U.S. EPA notes WMWI's concern. However, the first phase of the cleanup plan at the Hagen Farm Site, referred to as the Source Control Operable Unit (SCOU), addressed remediation of contamination in the landfill and in the sub-waste soils (vadose zone) immediately beneath the landfill. The cleanup plan for the SCOU involved capping the landfill and operating an in-situ vapor extraction (ISVE) unit. The landfill cap is expected to be effective in preventing the leaching of contaminants from the waste mass and the vadose zone to the groundwater via infiltration of precipitation. The ISVE is a system designed to remove contaminants from the sub-waste soils (vadose zone) and from the groundwater near the water table which would include the capillary fringe (zone). Therefore, this concern appears to lack relevance at the Hagen Farm Site.

U.S. EPA notes WMWI's concern over the DNAPL issue. However, based on the results of the RI, U.S. EPA does not believe DNAPL's exist at the Site. However, ROD text which was presented earlier in this response can be used to address the limitations of an extraction system due to the presence of a DNAPL.

COMMENTS:

WMWI comments that U.S. EPA and WDNR appear to have arbitrarily assigned the limits of waste as the point of compliance for the Hagen Farm Site with little regard to recent precedent within Region V and the State of Wisconsin which dictates the property boundary and/or design management zone (DMZ) as the correct point of compliance. WMWI requests that U.S. EPA and WDNR establish a point of compliance application consistent with NR 140.22 for the Hagen Farm Site.

SUPPORTING STATEMENTS:

WMWI cites numerous RODs throughout the country that have selected varying locations as points of compliance. Some points include the boundary of the landfill property, the landfill property boundary with performance monitoring to be located downgradient but beyond

the zone of influence of the extraction wells, slightly downgradient of the landfill itself, facility property line, and the DMZ or the property boundary whichever is closer to the waste boundary.

RESPONSE:

The U.S. EPA has been consistent in applying NCP Section 300.430(f)(5)(iii)(A). The U.S EPA, through the NCP, established the waste management boundary as the point where remediation levels generally shall be achieved at Superfund Sites. Once standards are met at the waste management boundary, the U.S. EPA believes protectiveness has been achieved for the pathway of concern. The NCP allows that the specific location of the point of compliance could vary from site to site based on site-specific conditions. U.S. EPA believes it to be appropriate and necessary to apply the point of compliance at the waste management boundary for the following reasons. First, at the Hagen Farm Site, the surficial aquifer and bedrock are hydraulically connected and potential exists for contaminants to be drawn from the upper aquifer into the lower aquifer. Given this scenario, U.S. EPA believes that the most conservative point of compliance (the waste management boundary) is necessary to limit the impact of the upper aquifer on the lower aquifer. Secondly, for Superfund response actions in Wisconsin being conducted in accordance with the NCP, the goal is to reduce groundwater concentrations throughout the aquifer(s), so that PALs are not attained or exceeded. If waste is to be left in-place at the conclusion of a response action, NR 140 standards (i.e., PALs) should not be attained or exceeded at the waste management boundary and beyond.

COMMENTS:

WMWI comments that the technology selection for on-property groundwater treatment should be made after an analysis of the off-property groundwater. Use of biological treatment for the on-property groundwater may be practical only if the off-property groundwater is treated separately from the on-property groundwater. If the off-property groundwater can best be treated in a combined stream with the on-property groundwater, biological treatment may not be a compatible technology. The dilution caused by the addition of the off-property groundwater may disrupt and potentially inhibit the effectiveness of the bacteria critical to the successful application of the activated sludge technology specified for the on-property groundwater.

RESPONSE:

U.S. EPA believes that a delay in making a decision at the Hagen Farm Site to determine if off-property groundwater can best be treated in a combined stream with the on-property groundwater would not be a prudent or responsible decision. A delay in the Agency's

decision may result in further degradation of the aquifer's quality and may increase overall costs of a remedy. Use of biological treatment for the on-property groundwater has been proven to be technically implementable and cost effective. In addition, U.S. EPA does not believe that selection of the on-property treatment technology is dependent on selection of the off-property treatment technology.

U.S. EPA would consider "other comparable technology" only if additional information and proposals developed in investigation of the off-property plume clearly documents that effluent quality and percent pollutant removal would be equal to or better than current wmwI projections for biological treatment (with pretreatment for metals). U.S. EPA has selected the biological treatment option based on WMWI projections of effluent quality based on treatability studies. Please note that "other comparable technology" does not include air stripping as discussed in WMWI's comments on a cost/benefit analysis.

COMMENTS:

WMWI requests that WDNR, when developing final surface water discharge limits for the Hagen Farm Site, give careful consideration to developing realistic, consistent, economically achievable standards with full understanding that the protocols used to develop the Hagen discharge limits must be consistently applied to other industrial and municipal discharges throughout the State.

RESPONSE:

U.S. EPA recognizes that at CERCLA sites where technology-based controls are not adequate to achieve water quality standards in the receiving water body or no water quality standards have been established (i.e., THF), numerical and/or narrative standards must be developed which are site specific. However, U.S. EPA must emphasize that the goal of the discharge standard is to ensure that substantive requirements for discharge to surface waters are met in order to maintain the chemical, physical, and biological integrity of the receiving water body. U.S. EPA also recognizes that technology based limits must be developed carefully. Therefore, U.S. EPA shall take the most conservative approach to achieve that goal.

Additional comments on specific WMWI concerns are presented below:

The example cost benefit analysis presented in Waste Management's comments is not accepted as valid since air stripping technology is not an acceptable treatment technology based on projected low pollutant removals (up to 40% THF in the example) and projected high effluent concentrations.

- WDNR notes that the "general" permit for discharge of treated contaminated groundwater does not apply to all groundwater remedial action projects. A more restrictive specific WPDES permit is required if water quality based limits and requirements are more restrictive than limits in the "general" permit or at the discretion of the Department. Therefore, the use of the general permit for appropriate LUST discharges does not preclude implication of more restrictive discharge limits. Generally, many LUST cases involve relatively minor remediations and low discharge volumes in comparison to more complex superfund remediations. Reference to the Model EPA permit for discharges from the cleanup of gasoline released from underground storage tanks will verify that the Department selected the least restrictive of the BTEX limits in EPA's model permit which were recommended for the smaller remediations (ie., gas stations, etc.) for the "general" permit. It is notable that EPA's Model NPDES permit recommended more restrictive limits of 5 ug/L for Benzene and 100 ug/L for total BTEX as well as biomonitoring for more significant gasoline cleanups.
- Background surface water quality must be accounted for in the development of water quality based limits in accordance with Wis. Stats. and Administrative codes referenced above.
- Chapter NR 140. Wis. Admin. code (WAC), groundwater standards PALs are not specified as limits for discharges However, effluent limits for to surface water. discharges to surface water developed in accordance with Chapter 147 Wis. Stats. and NR 102, 103, 104, 105, and 207, WAC, may be more or less restrictive than NR 140 depending on site specific consideration and PALS pollutants being evaluated. Technology based discharge limits and requirements specified in accordance with NR 220, WAC, may also be more restrictive than NR 140 PALs. If there is any component of a surface water discharge to groundwater, the more restrictive of NR 140 PALs, surface water quality based limits or technology based requirements are applicable, as is the case for discharge to the drainage ditch adjacent to the Site. Reference to example discharge limits in Table 1 of Waste Management's comments illustrates this for several pollutants.

COMMENTS:

WMWI asserts that the risk estimates presented in the Baseline RA, which were prepared in accordance with U.S. EPA methodologies and specifications, do not reflect the true or reasonable estimates of site risks. WMWI maintains that risk estimates prepared under

current U.S. EPA risk assessment guidance are inflated, thus unnecessarily alarming the public and diverting attention from other more important environmental problems. Furthermore, WMWI suggests that U.S. EPA should consider using the results of a report entitled "Alternative Methodology Risk Assessment of the Groundwater Ingestion Pathway at the Hagen Farm Landfill" in selecting an appropriate remedy for the Site. This report was submitted with WMWI comments. WMWI feels that the methodologies in that report more accurately depict and quantify the risks at the Hagen Farm Site as compared to U.S. EPA's approach. WMWI suggests that the report supports the conclusion that more than likely no adverse health effects would be expected from the Site if the groundwater were to be consumed as a drinking water supply.

SUPPORTING STATEMENTS:

- * WMWI asserts that the Region V policy has not been authorized by U.S. EPA Headquarters, and, in fact, is inconsistent with current U.S. EPA national Superfund risk assessment guidance, and U.S. EPA's proposed exposure-related measurement and final exposure assessment guidelines. WMWI quotes U.S. EPA "Risk Assessment Guidance for Superfund, Volume I, Human Evaluation Manual (EPA/540/1-89/002, December 1989)" (p. G19) ...assuming long-term contact with the maximum concentration is not responsible. WMWI asserts that this is precisely the effect of following the Region V policy, which WMWI asserts uses an implausible worst-case analysis as the only level of analysis.
- * WMWI presented quotes from U.S. EPA "Proposed Guidelines for Exposure-related Measurements" (53 Federal Register 48830, December 2, 1988) as follows:
- A legitimate use of worst case scenarios is to determine if the exposure or risk is low enough even at this extreme so as to dismiss concern for this scenario. It is not legitimate to use a worst-case scenario to prove that there in fact exists a concern in a real population.
- If the exposure or risk value estimated by a worst-case scenario is high enough to cause concern, the assessor must reevaluate the parameters used and perform reality checks before deciding a problem really exists.
- * WMWI presented a quote from U.S. EPA "Guidelines for Exposure Assessment" (57 Federal Register 22888, May 29,1992) as follows:
- ...the only thing the bounding estimate can establish is a level to eliminate pathways from further consideration. It cannot be used to make a determination that a pathway is significant... and it certainly cannot be used for an estimate of actual exposure...

RESPONSE:

The methods used in the U.S. EPA "Risk Assessment Guidance for Superfund, Volume I, Human Evaluation Manual" to calculate risks at the Site have been developed by the U.S. EPA. acknowledges that the assumptions used in our risk assessments are conservative. The assumptions are designed to be reasonable and The assumptions are conservative because the not worst case. Superfund program has always designed its remedies to be protective of all individuals and environmental receptors that may be exposed at a site; consequently, U.S. EPA believes it is important to include all reasonably expected exposures in its risk assessment. Again, U.S. EPA believes the assumptions used in the guidance referenced above to calculate risks are reasonable and necessary to determine whether action to be taken needs to be taken at a site in order to adequately protect human health and the environment. The risk assessment guidance referenced above is designed to focus the assessment on more realistic exposures. U.S. EPA has adopted these positions and policies and has not revised the regulation. addition, the U.S. EPA guidance states that if good data identifying the center of the plume do not exist, modeling is not performed, and the collection of additional samples is precluded, generally the well with the overall highest concentration of contaminants of concern should be used as the exposure point concentration. At the Hagen Farm Site, the well with the overall highest concentration of contaminants of concern was used as the exposure point concentration. This is reasonable and does not constitute a worst case or "inflated" risk because it is not likely that under these conditions the true highest contaminant concentration has been detected in sampling.

The Human Health Evaluation Manual fully supports the Regional guidance as shown on page 6-27, "Selection of the location(s) used to evaluate future groundwater exposures should be made in consultation with the RPM." Also, Headquarters expects the Regions to determine the appropriate exposure area for use in calculating the exposure point concentration. Other Regions have adopted similar guidance.

U.S. EPA acknowledges the results from the report entitled "Alternative Methodology Risk Assessment of the Groundwater Ingestion Pathway at the Hagen Farm Landfill" submitted to U.S. EPA. However, U.S. EPA believes that using the results of the report, as suggested by WMWI, would not be appropriate for determining whether remedial action is warranted at this Superfund Site. With respect to risk assessments, U.S. EPA is obligated to follow Agency policy as opposed to recommendations or suggestions from PRPs or outside sources in order to consistently carry out the requirements of CERCLA. Therefore, U.S. EPA will continue to use the results of the Risk Assessment developed for Hagen Farm under U.S. EPA guidance to justify the need to take remedial action at the Site.

COMMENT:

Second bullet under paragraph "Remedial Action Goals" (page 6, RGCP) states that the goal of the remedy selection process is "to restore groundwater on and off-property so that contaminant levels meet state groundwater standards." WMWI comments that the affected groundwater on the property is not a source of drinking water and, according to NR 112.08, installation of private wells is restricted within 1,200 feet of the landfill. Additionally, property deed restrictions which are currently recorded will prohibit construction of on-property drinking water wells. The FS cited as a remedial action objective goal to "reduce the groundwater contamination beneath the Site to a technically feasible level producing acceptable health risk levels, and to attain compliance, where possible, with identified Federal and State ARARS". WMWI asserts that the restoration goal as described by U.S. EPA in the RGCP may be misleading to the public. WMWI requests that U.S. EPA acknowledge the low likelihood of complete groundwater restoration to WDNR groundwater standards as described by the RGCP.

RESPONSE:

- U.S. EPA reaffirms its goal as stated in the RGCP (i.e., restoration of the aquifer on-property) for the following reasons:
 - Although WMWI is correct in stating that NR 112.08 allows for restriction on installation of private wells within 1,200 feet of a landfill, it should be noted that zoning cannot guarantee that no wells will be allowed in the area in the future. Because the State has the ability to grant variances under Section NR 112.43 from supply well restrictions, future prohibition of the use of the groundwater for drinking water purposes by the State cannot be guaranteed.
 - According to the NCP Section 300.430(e)(3)(ii), institutional controls may be used as a supplement to engineering controls over time, but should not be substituted for active response measures as the sole remedy unless active response measures are not practicable. If it could be demonstrated that the aquifer will cleanse itself within a reasonable period of time, U.S. EPA could possibly consider that as a viable option. However, natural cleansing is not expected to occur within a reasonable period of time at the Hagen Farm Site.
- U.S. EPA acknowledges WMWI's concern over the likelihood of complete groundwater restoration to WDNR groundwater standards and that the restoration goal as described in the RGCP may be

misleading to the public. As stated earlier, U.S. EPA is confident that the groundwater extraction and treatment component of the selected remedy would have a high probability of success in terms of effectively withdrawing and removing contamination from the groundwater at the Hagen Farm Site to WDNR groundwater standards. However, U.S. EPA will inform the public if, after operation, it is determined that it is not technically feasible to meet ARARS.

COMMENT:

WMWI feels that further clarification of Section 4 "Reduction in Toxicity, Mobility, or Volume Through Treatment" (page 7, RGCP) is required. The paragraph states "Alternative 2 would increase the rate of cleanup by using micro-organisms injected into the groundwater to help treat the contaminants into chemicals that are not harmful." It should be noted that Alternative 2, since it will accelerate cleanup, will not necessarily operate for 30 years as it is traditionally assumed.

RESPONSE:

U.S. EPA interprets the comment regarding the necessity for clarification as involving the cleanup time frame. Therefore, U.S. EPA acknowledges WMWI's comment and notes that by using microorganisms injected into the groundwater to accelerate cleanup, Alternative 2 may not necessarily operate for 30 years as it is assumed for costing purposes.

COMMENT:

wmwI states that the section "Compliance with ARARS" (page 7, RGCP) is misleading as written. WmwI asserts that U.S. EPA's representation that the remedy will meet all ARARS is misleading. The Draft Final Feasibility Study contained text discussing the potential future need for development of ACLs and/or a NR 140 ARAR waiver based upon technical impractability from an engineering perspective. This text was included in the draft final Feasibility Study as required by the National Contingency Plan (NCP) for sites where it is recognized that the remedy may not meet ARARS. WmwI states that the NCP requires that the potential for an ARAR waiver be identified in the Feasibility Study and be summarized in the Proposed Plan when it is released by the U.S. EPA.

RESPONSE:

Based on information obtained during the RI, and on careful analysis of all remedial alternatives, U.S. EPA is confident that the groundwater extraction and treatment component of the selected remedy would have a high probability of success in terms of effectively withdrawing and removing contamination from the groundwater at the Hagen Farm Site. In addition, there is no evidence to demonstrate that a groundwater pump and treat system

<u>cannot</u> restore the aquifer at the Hagen Farm Site to Wisconsin NR 140 standards, even at the point of compliance. For these reasons, extraction and restoration of the plume in the aquifer is expected to be technically feasible.

The ability to achieve cleanup goals at all points throughout the area of attainment, or plume, cannot be determined until the extraction system has been implemented, modified as necessary, and plume response monitored over time. This includes the area in the immediate vicinity of the contaminants' source, where concentrations are relatively high. Therefore, U.S. EPA will continue to believe that clean-up standards are achievable until the system, during operation, demonstrates otherwise. If during operation it is determined that it is not technically and economically feasible to achieve the PALs for a specific substance an Alternative Concentration Limit (ACL), may be established by U.S. EPA. Language reflecting this option shall be provided in the text of the ROD.

COMMENT:

WMWI feels that the in-situ vapor extraction system (ISVE) discussed on page 4 of the RGCP is inaccurate with respect to the proposed installation at Hagen Farm. Air injection is not appropriate for the Hagen Farm Site and as such, is not being considered. Therefore, WMWI requests that U.S. EPA correct this statement on the RGCP.

RESPONSE:

U.S. EPA recognizes the inaccuracy in the RGCP concerning the statement about air injection. Air injection was not considered. The statement should read, "The ISVE system works by removing volatile chemicals in the unsaturated waste/sub-soils without excavation. The process moves air through the Waste/sub-soils near hydrocarbon contamination using a vacuum pump."

COMMENT:

In reference to the discussion on page 5 of the RGCP concerning drinking groundwater from the immediate vicinity of the site, WMWI states that it should be noted that all private wells on-property have been abandoned according to state regulations and are no longer available as drinking water supplies.

RESPONSE:

U.S. EPA recognizes WMWI's statement and hereby notes that all private wells on-property have been abandoned according to state regulations and are no longer available as drinking water supplies.

U.S. EPA ADMINISTRATIVE RECORD INDEX

UPDATE #3

HAGEN FARM SITE

STOUGHTON, WISCONSIN

05/14/92

120	SATE	AUTHOR	RECIPIENT	TITLE/DESCRIPTION	PAGES
:	00/0 0/00			Explanation of Significant Differences: Change to the Resedy in the 1990 ROD with Supporting Documents	53
2	9079 0 790	Antens, I., USEPA	Dowden, j., Waste Management	Notice of Deliquency	2
;	01/25/90	Antens. I USEPA	Dowden, J., Waste Managesent	Invoice for Recovery of Costs	21
ı	04/25/90	Harrity, D., PRC	iee. J., USEPA	Preliminary Risk Assessment Review	4
5	05/08/90	Antens. I., USEPA	Brncich, D., Waste Management	Letter Providing Revised Invoice for FY 1989 Oversight Costs	2
5	06/06/90	Jacobs. P., Warzyn	Lee. J úSEPA	Groundwater Sampling while Drilling at Boring 8-328	2
7	06/14/90	Jacobs, P., Warzyn	Brncicn. D., Waste Management	Meil installation Procedures	2
3	93786/99	USEPA		Fact SheetUS EPA Issues Proposed Plan for - Landfill Cleanup	12
Ŷ	07/20/90	covejoy. M. & Asbury, G., Wayzyn	Lee. J., USEPA	Letter re: Degree of Expected Reductions of VOCs (per FS)	2
16	08/ 00/90	Wisconsin Dept. of Health & Social Services		Health Information Newsletter	4
11	08/15/90	Brncich, D., Waste Managesent	Lee. J., USEPA & Evanson. T., WDNR	issues for 8/23/90 Meeting with Attachments	10
12	08/17/90	Antens. I., JSEPA	Brncich, D., Waste Management	Letter Providing Documentation for Jacobs Contract for Billing Period 10/1/88-9/30/89	1
13	08/28/90			Heeting Notes for magen Farm KirS	6
;4	10 31/40	Asbury, B., Warzyn	Les, J., USEPA	Cover Letter to work Flan Addenoum, dagen Farm RI FE	<u>:</u>



			PECIPIENT	- MALENDESCADE FOUX	
	70.76	אטא טא			:::::
::::	::::	:::::::			
.:	10, 10, 70	Evanson, I., WDNA	Lee, J., ISEPA	Comments on the $10/2/90$ mork filan Addenous. Hagen farm RI/FS	å
12	17 13 93	_ovejoy、音。 #arzyn	iee, J., USEPA	Revision to Work Flan Addengum, magen Farm	á
:*	19/12/99	Stram. A., Counsel. Waste Management of Wisconsin	Sullickson, A., Property Swher	Consent for Access and Entry	4
18	10.1a/90	Evanson, 7., ¥ÛNR	Asbury, 6., Warzyn	variance to NR 141.19. Borenoie Diameter for Pump Test Monitoring Wells	:
19	10/22/96	Asbury, B., Wayzyn	Lee. J USEPA	Cover Letter to Work Plan Addendum and Attachments	1
70	10, 23/90	Evanson, 7., WDNR	Asbury, G., Wayzyn	Logging of Soil Boreholes During Phase II Orilling Activities	2
21	11. 26/90	Burge. D., Versar. Inc.	Lee, J., USEPA	Report of Drilling incident	2
22	11/30/90	Brncich. D., Waste Management	Evertt, D., Stoughton Conservat- ion Club	Request to Prohibit use of Target Practice Range During Testing	5
23	12.03/90	Brncich. D Waste Management	Lee, j., USEPA	Report of Drilling incident	4
24	12/04/90	Lae, J., USEPA	Brncich, D., Waste Management	Approval of Work Plan Addendum	1
25	12/06/90	Brncich. D Waste Management	Les, J., USEPA	Monthly Progress Report: November 1990	63
25	12/11/90	Evanson, T. NDNR	Brncich. D., Waste Management	Aquifer Pump Test and Carbon Treatment of Effluent Requirements	5
27	12/17/90	Brncich, D., Waste Management	iee, J., USEPA	Report of Aquifer Puep Test	2
28	12/17/90	Jordan-Izaguirre, D., ATSDR	Lee, J., USEPA	Private Weils Results	86
29	01/07/ 9 1	Brncich, D., Waste Management	Lee. J., USEPA	Hagen Fare Aquifer Pump Test Preliminary Report	46
30	01/07/91	Brncich, D., Waste Management	Lee, J., ÜSEPÄ	Monthly Progress Report: December 1990	84

			NEW MARIE	TITLE / DESURIPTION	- HOE 3
1004	JA E	म्यामणस			:::::
:::=	::::	11111			
71	21/14/71	Antens, i., USEPA	Brncich, D., Waste Management	Invaice for Recovery or losis	Ţā
::	12/07/91	Hinstein. M. Waste Haragement	Lee. J., USEPA	Cover Letter to Treatablilty Study work Plan	1
••	32/11/91	Brncich, C., Waste Management	lee. J., USEPA	Water Quality Results for Manganese and TCL Seel Volatiles	19
74	02/15/91	Brncich, D., Waste Management	Lee, J., USEPA	Response to Comments or versar, inc. on Treatability Study mork Plan	2
75	02/20/91	Vanderpool, E., USEPA	Lem. J., ESEPA	Geological Review Comments of Treatability Study Work Plan	1
76	02/28/91	Évanson, T., WDMR	Lee. J., USEPA	Comments on Treatability Study Work Plan	2
37	02/28/91	Harrity, J., PRC	Lee, J., USEPA	Cover and Review of Treatability Study Work Plan	ð
38	03/04/91	Brncich. D., Waste Management	cee, J., USEPA	Clarification of Severa. Items in Treatability Study work Flan	2
39	03/05/91	Lee. J., USEPA	Brncich. D., Waste Managesent	Approval of Work Flam	2
49	03/07/91	Holoska, T., U.S.EPA	Lee. J USEPA	Comments on Treatmollity Study Work Plan	2
41	03/15/ 9 1	Brncich, D., Waste Management	cee, J., USEPA	Request for Letter Granting Approval for Sample Collection	i
42	03/21/91	Brncich, D., Waste Management	cee, J., USEPA	Response to Comments on Treatability Study Work Plan	30
_ 43	03/ 26/91	Evanson. T., WDNR	Lee, J., USEPA	Waste Management's Compliance with WDNR Hazardous Waste Rules for Collection/Transportation of Hazardous Waste Samples	i
44	03/ 29/91	Vanderpool. L. U.S. EPA	Lee. J., USEPA	Review of Waste Managements Response to Comments on Work Flan	1
45	04/15/91	Evanson, F., WDMR	drek. J., Waste Management	Collection/Transportation of Groundwater for Treatability Studies	2
46	64/15/91	Urek. J. Waste Management	Evanson, T., #BNR	Request for variance of mONR Hazardous waste Rules for Collection/Transportation of Hazardous Waste Samples for Treatability Studies	Ó

				TIMES DESCRIPTION	Р वह र 5
	JE: F	#ULHUK	PEUTPIENT	1000 DECEMBERATION	:::32
::::	****	::::::	11311111	***********	
4-	04,24,71	Evanson, T., WDNR	Lee, J., USEPA	Reassignment of State Project Manager	1
46	05/07/91	Brncich, D., Waste Management	Lee. J uSEPA	Monthly Progress Report: April 1991	84
14	05/23/91	covejoy. M., Wayzyn	Lee. J., USEPA	Cover Letter to Prefinal Landfill Cover Design Report	i
<u>51</u>	05/30/91	Termont-Schenk, S., Wayzyn	Lee, J., USEPA	Dover Letter to Full-Size Design Drawings	1
51	96/00/91	warzyn Inc.	Waste Management of Wisconsin, Inc. & Lee, J., USEPA	RD/RA morx Plan: Remedial Design/Remedial Action: Source Control Operable Unit	56
52	06/04/91	Baumann, A., USEPA	Lee, J., USEPA	Review Comments on Health & Safety Plan	1
J.	06/06/91	Thomas, C. USEPA	Lee, j., USEPA	Review Comments on Pretinal Landfill Cover Design Report	4
54	06/13/91	Dune, J. WONR	Lee, J., USEPA	FAX-Comments on RD/RA Prefinal Design Report	1 .
55	06/25/91	Bandhi, B., PRC	Lee, J., USEPA	Review Comments on Prefinal Landfill Cover Design Report	1
56	07/00/91	Wayzyn inc.	Waste Management of Wisconsin, Inc. & Lee, J., USEPA	Landfill Cover Design: Remedial Design/Remedial Action: Source Control Operable Unit	335
57	377 32/91	Lae, J., USEPA	Brncich, D., Waste Managesent	Review Comments on Prefinal Landfill Cover Design Report	5
58	07/15/91	Lee. J., USEPA	Brncich, D., daste Management	Review Comments on Technical Memorandums 3 and 4	14
59	07/24/91	Versar. Inc.	Lee, J., USEPA	Technical Review of Baseline Risk Assessment Plan. Remedial Investigation/Feasibility Study	6
60	08/00/91	USEPA		Fact SheetProgress Report	ò
òi	08/01/91	Termont-Schenk, S., Wayzyn	Lee, J USEPA	Cover to Final Landfill Cover Design Report	1
62	08/05/91	Termont-Sh a nk, S., Wayzyn	Lee, J., USEPA	Responses by mayzyn and Waste Management to Agency Comments on Prefinal Landfill Cover Design Report	18

	JA'E	MOUTHOR	RECORDERY	TITES/DESCRIPTION	*#053
522	1222		11111111	:::::::::::::::::::::::::::::::::::::::	12222
52	[6, [4/7]	_ae. j USEPÅ	Brncich, B., Waste Management	Approval of Final Landfill Cover Design and use of Rosenbaum Clay Soils for Landfill Cover	2
24	18/27/91	Stram. A., Waste Manageaent Counsei	Everett, 0 Stoughton Corservat- ion Club	Consent for Access and Entry	3
, 6 5	08/27/91	Straw, A., Waste Management Counsel	Guilickson, F.	Consent for Access and Entry	3
50	08/27/91	Straw. A., Waste Management Counsel	Sagmoen, C.	Jonsent for Accèss and Entry	2
5 7	08/27/91	Straw, A., Waste Management Counsel	Sjertson. M.	Consent for Access and Entry	2
66	08/27/91	Straw. A., Waste Management Counsel	K Way Insulation. inc.	Consent for Access and Entry	2
69	08/27/91	Straw, A., Waste Management Counsel	Sundby Sand & Gravei	Consent for Access and Entry	2
70	08/27/91	Straw. A., Waste Management Counsei	Sundby, 6.	Consent for Access and Entry	3
71	08/29/91	U.S.EPA		Public Heeting Agenda	1
72	08/30/91	Moser, I., Wayzyn	Lpe. J., USEPA	Cover Letter to Braft RI Report	i
73	09/05/91	Lee, J., USEPA	Addresses	Copies of Draft Remedial Investigation Report	1
74	09/10/91	Sundby, S., Property Owner	Waste Management	Fax-Signed Consent for Entry and Access	1
75	09/11/91	Termont-Schenk, S Warzyn	Lee. J., USEPA	Responses to Agency Review Coments on Technical Memoranda Nos. 1-4	3
76	09/26/91	Jirik, A., Versar, Inc.	Lee, J., USEPA	Review Comments on Draft RI	2
77	09/26/91	Nisconsin State Laboratory of Hygiene	Evanson, T., HDMR	Sampling Results of Private Wells	29
78	09/30/91	Moser. J., Wayzyn	Lee, J., USEFA	Private Well Supply Sampling	7
79	10/02/91	Matheson, T., USEPA	Figliula, I., USEPA	Review Comments on Draft RI Report	1
50	10/ 08/ 91	Schnoes, K., PRC	Lee, J., USEPA	Fax-Versar's Review Comments on Draft RI Rep-	8

:

		<u> </u>		THE RESERVENTEN	-x6E2
	CATE	AUTHUR	PECIFICAL	THE SECURITY TOWN	:::::
::::	::::	::::::	::::::::::		
āi	10/08/91	Lee, J., JSEPA	Brncicn. D., maste Management	Review Comments on Graft RI Report	¥.7
81	10711791	Watters. E. USEPA	Niedergang, N., USEPA	Water Division Review of Braft RE Report	:
30	10/16/91	Harrity, D., FRC	Tur so nt, S., Mayzyn	Cover to Ri Review Comments by Versar	1
84	11/00/91	Wavzyn Inc.	waste Management of Wisconsin. Inc. & cee, J., USEPA	Final Remedial investigation Report: vol. 1 of 4 - Tex. Tables and Figures	105
85	11/00/91	Wayzyn inc.	Waste Management of Wisconsin, Inc. & Lee, J., USEPA	Final Remedial Investigation Report: Vol. 2 of 4 - Appendices A-C	5 6 0
36	11/00/91	Wayzyn inc.	Waste Management of Wisconsin. Inc. & Lee. J., USEPA	Final Remedial Investigation Report: Vol. 3 of 4 - Appendices D-I	412
87	11/00/91	Wayzyn inc.	Waste Management of Wisconsin, Inc. & Lee, J., USEPA	Final Remedial Investigation Report: Vol. 4 of 4 - Appendices J-M	350
88	11/04/91	Hoser, J., Wayzyn	Lee. J., USEPA	Conference Call Report of Draft RI	2
89	11 '22/91	Moser, J. & Termont-Schenk, S., Wayzyn Inc.	Lee, J., USEPA	Responses to Agency Review Comments on Draft RI Report	22
90	01/00/92	Warzyn Inc.	Waste Management of Wisconsin, Inc. & Lee, J., U.S. EPA	In-Situ Vapor Extraction Pilot Study Work Pl- an: Remedial Design/Remedial Action: Source Control Operable Unit	32
71	01/20/92	PRC Environmental Management, Inc.	Lee, J., USEPA	RD/RA Oversight Trip Report 2	92
92	01/24/92	Antens. I., USEPA	Brncich. B., Waste Managesent	Invoice for the Recovery of Costs	37
93	01/31/92	Termont-Schemk, S Wayzyn Inc.	Lee, J., USEPA	Responses to U.S. EPA Comments on Draft FS	75
94	02/10/92	Warzyn Inc.	Lee. J., USEPA	Responses to Comments on the Draft in Situ Vapor Extraction Pilot-Study Work Plan	48
95	03/ 02/92	Niemann, C., Waste Management	Distribution	February 19, 1992 Recting Issues	4
₹6	03/02/92	Heinrich, B., Waste Management	Lee. J., JSEPA	Meeting Notification re: Draft Feasibility Study	1

	DATE	AUTHUR	RECIPIENT	TITLE/DESCRIPTION	23652
****	iiii Am (E	12222	=======================================	:::::::::::::::::::::::::::::::::::::::	:::::
97	3 1 79 6/92	Heinrich, B., Waste Management	Simmons, / USEPA	Documentation Deficiency on Oversight Cost Bill (1/24/92)	•
48	337 9€192	Niemann. I., Waste Management	cee. J., JSEP∺	Format for Revised 8000 Feasiblist/ Study	2
79	03/08/92	Cee. J., USEPA	Niemann, C., Waste Management	Review Comments for BCGU Revised Feasibility Study	30
100	03/09/92	Niemann, D., Waste Management	Lee, J., USEPA	Revisions to Draft Final GCOU Feasibility Study	1
101	03/16/92	Niesann, C., Waste Management	Lee, J., USEPA	Comments on ROD with Sample ROD	90
102	03/16/92	Miemann, C., Waste Management	Lee, J., JSEFA	Progress Letter on In-Situ Vapor Extraction	2
- 103	03/17/92	Sandhi. B., PRC	Lee, J., USEPA	RD/RA Oversignt Trip Report 3	22
104	03/20/92	Mienann, C., Waste Management	Distribution	March 11. 1992 Meeting issues	3
105	13/30/92	Termont-Schent, S., Warzyn	Pfeiffle, D., US Arey Corps of Engineers	Request for response re: Wetland issues	i
104	03/71/92	6and≈1, 3., PRC	Lee, j., USEPA	Acknowledgement of PRP Remedial Action Implementation Report	i
:07	34100792	Warzyn, Inc.	Waste Management & Lee, J., USEPA	Final Feasibility Study for Groundwater Control Operable Unit	402
108	04/08/92	Law, J., USEPA	Niemann, C., Waste Hanagement	Review Comments on 3 Chapters of Draft FS	13
109	04/27/92	Termont-Schenk, S Warzyn	Lee, J., USEPA	Responses to Comments on the Draft Final Feasibility Study	68
	·		•		

;

U.S. EPA ADMINISTRATIVE RECORD INDEX

UPDATE #4

HAGEN FARM SITE

STOUGHTON, WISCONSIN

09/08/92

2308	2AT E	AUTHOR	RECIPIENT	TITLE/DESCRIPTION	PAGES
1	06/11/92	U.S.EPA	Pad ov ani, S., U.S. IPA	Public Meeting: Transcript of Procesoings	57
2	97/ 30/92	Brncich. D. & Seglin, L., Waste Management of Wisconsin, Inc		Comments on the Recommended Ground Mater Cleanup Plan	112.



State of Wisconsin

DEPARTMENT OF NATURAL RESOURCES

101 South Webster Street Box 7921 Madison, Wisconsin 53707

SUPERFUND/SOLID WASTE FAX 608-267-2768 TELEPHONE 608-266-2621

Carroll D. Besadny Secretary

September 28, 1992

Mr. Valdas V. Adamkus, Administrator U.S. EPA Region V 77 W. Jackson Chicago, Ill 60604

SUBJECT:

Concurrence on The Selected Groundwater Control Remedy,

Hagen Farm Site, Town of Dunkirk, Dane Co., WI

Dear Mr. Adamkus:

The Department is providing you with this letter to document our concurrence with the remedy selected for the groundwater control operable unit at the Hagen Farm Superfund site. The proposed groundwater remedy, as outlined in the June, 1992 Proposed Plan, will address the contaminated groundwater both on and off site, and is considered the final remedy for the groundwater at the site. The selected remedy is alternative 2, which includes:

- * Groundwater use restrictions in the form of deed restrictions to the extent necessary to implement and protect the remedy;
- * Installation of a fence around the treatment system;
- * Additional monitoring to determine the depth and extent of off-site contamination;
- * A series of groundwater extraction wells both on and off-site designed to actively restore the groundwater in both areas;
- * Pretreatment of all extracted groundwater for the removal of metals and inorganic solids;
- * Treatment of the on-site extracted groundwater in an activated sludge biological treatment facility constructed at the Hagen Farms site;
- * A bench scale study examining the feasibility of injecting the treated onsite groundwater into the aquifer below the site in order to enhance in-situ bioremediation;
- * Treatment of off-site extracted groundwater using an appropriate treatment technology. This technology has not yet been determined but options include cascade aeration, activated sludge, air stripping, granular activated carbon (GAC) or UV-oxidation;



- * Treatment of residue, sludge, and/or spent coagulates to meet land disposal requirements, followed by disposal in a RCRA landfill; and
- * Discharge of all treated groundwater to the Yahara River or nearby wetlands.

The range of costs for the selected remedy are estimated to be as follows:

Capital Cost \$ 4,396,000 - \$6,288,000 Annual O&M 1st year \$ 550,000 - \$ 1,062,000 Total Present Worth \$ 13,612,000 - \$ 24,163,000 Estimated time to implement 30+ Years

Though the Department concurs with the selection of this remedy, WDNR concurrence is based upon the understanding that at the time the proposed treatment design is finalized, the effluent discharge limits and discharge location (including any reinjection of enhanced groundwater which is proposed) are acceptable to the WDNR and are in compliance with the effluent discharge limit requirements of Chapters NR 102, 105, 106, 207 and 220, the wetlands protection in Ch NR 103, and the applicable air quality standards in Chs NR 400 to 499, WAC. Our concurrence is also conditioned on EPA's supplementation of that portion of the administrative record that pertains to off-site groundwater extraction and treatment with all documents submitted by the WDNR in the future dealing with off-site groundwater extraction and treatment, in accordance with 40 CFR 300.825(a)(l). In addition, the Department recommends that the potential to discharge to a municipal sewerage system be further investigated during the remedial design.

We understand that if the potentially responsible parties (PRPs) do not agree to fund the remedy, it will be necessary for the State of Wisconsin to contribute 10% of the remedial action costs associated with the actions and 10% of the 0&M costs for the first 10 years of groundwater extraction and treatment. In addition, if the PRPs do not agree to fund the 0&M, the State of Wisconsin will need to contribute 10% of all other 0&M costs for the first year and provide for all 0&M after that, provided that no changes to the National Contingency Plan are made that would require an alternative cost allocation. We provide assurance of the State's willingness to provide this required state cost share on the assumption that U. S. EPA will pursue all feasible enforcement actions against the PRPs prior to expending the Fund at the site.

We understand that if the Fund is expended to conduct the remedy and if hazardous waste needing disposal is required to be managed off-site as part of the remedy, that the State of Wisconsin will be required to provide the assurances for hazardous waste management in §40 CFR 300.510(d) and (e) of the National Contingency Plan. The assurances are that a compliant hazardous waste facility is available, and that facility's use is consistent with our approved Capacity Assurance Plan. In addition, the Department recommends that an analysis and a finding be made during remedial design on whether hazardous wastes can be managed in-state and on-site, to the extent practicable. Hazardous waste residuals may be generated by the pretreatment of extracted

groundwater prior to treatment, and sludge generated during the treatment of groundwater may constitute hazardous waste. We also understand that our staff will continue to work in close consultation with your staff during the pre-design, design and construction phases of the remedy.

Thank you for your support and cooperation in addressing the contamination problem at the Hagen Farm site. Should you have any questions regarding this matter, please contact Jane Lemcke, Superfund Remedial Unit Leader, at (608) 267-0554.

Sincerely,

C. D. Besadny Secretary

cc: Lyman Wyble - AD/5
Linda Meyer - LC/5
Paul Didier - SW/3
Mike Schmoller - SD
Mary Pat Tyson - U. S. EPA Region V, 5HS/11
Mark Giesfeldt - SW/3
Jane Lemcke - SW/3
Paul Kozol - SW/3